NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-A-1 TO A-A-5.
2. FOR COMPLETE 1/8" SCALE FLOOR PLAN, SEE DRAWING A-A-101
3. ALL ELEVATIONS GIVEN THUS (+0.0) ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEER'S DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG. A-A-6-204 AND A-A-6-205.
6. ALL TRENCH HEADERS TO BE PREFINISHED AT UNDERSIDE OF SLAB FOR A WIDTH OF 4'-0" WITH A SPRAY-ON TYPE OF PREFINISHING SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE & ELECTRICAL ENGINEER'S CONTRACTOR APPROVED SHOP DWGS. FOR LOCATION & EXTENT OF TRENCH HEADERS & PREFINISHING.
7. FINISH FLOOR ELEVATIONS AND TOP OF SLAB ELEVATIONS ARE (+0'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMENS TOILETS ONE EXPENSEAL. IF EACH LAVATORY ACCESS DOORS TO SOAP DISPENSER SHALL BE LOCATED IN ACCORDANCE WITH TILE CONTRACT. SEE TYPICAL TOILET DETAILS DWG. A-AB-206
9. WHERE NO SUPPRESSED CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS, STAIRS, ETC., BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE MAINTAINED AT 8'-2" ABOVE FINISHED FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: _____
11. CENTER REQUIRED ON ALL DRAIN PROJECTIONS OVER 6¾" NOMINAL ("A" ACTUAL) DIMENSION AT ELEVATOR SHAFTS AND SHALL BE MINIMUM 10'-0" P.C.F.M. HORIZONTAL. SEE TYPICAL DETAILS
12. FOR PREFINISHING OF FREE STANDING COLUMNS AND TYPICAL PARTITION REVALS SEE DRAWINGS A-AB-206 TO A-AB-208.

BUILDING NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT NO.	DRAWING	DATE 3-7-68	
	1-30-70	A-84	B.C.
	1-30-70	A-85	L.J.
	1-30-70	A-87	L.J.
	5-25-71	A-91	D.L.
	5-25-71	A-96	D.L.
6-1871 1-164	DGL	5-25-71	A-97	D.L.
4-1-71 4-188	LJT	5-25-71	A-93	D.L.
5-12-71 A-79	AM	8-1-66	A-10	R.G.
5-12-71 A-78	AM	6-10-66	A-5	R.G.
1-30-70 A-81	B.C.	6-1-66	A-3	R.G.

REVISIONS — NO. | DATE | BAL. NO. | BY

REVISIONS — NO. | DATE | BAL. NO. | BY

REGISTERED ARCHITECT — STATE OF NEW YORK — No. 17

APPROVED: CHIEF, PLANNING DIVISION — DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY — PLANNING, UTILITIES, FOUNDATIONS

TITLE: 66TH FLOOR CORE PLAN

SCALE: 1/8"=1'-0" — DATE: 3-7-68

DRAWING NO. A-A-105