NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DWG # A-1-1 TO A-1-6.
2. FOR COMPLETE DIMENSIONS AND NOTES IN FINE SPACES SEE 1/2 SCALE DWGS. # A-11-01
3. ALL ELEVATIONS GIVEN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL, ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DWGS.
5. FOR FLOOR, CEILING AND TOP OF SLAB ELEVATIONS SEE (SECT) UNLESS OTHERWISE SHOWN OR NOTED.
6. ALL WALLS AND PARTITIONS SHOWN WITH HATCHING ARE INCLUDED IN THIS CONTRACT. ALL WORK OUTSIDE PERIMETER WALL OF TOWER, SHOWN UNHATCHED IS IN A SEPARATE CONTRACT BY OTHERS. SHOP WORK BY OTHERS INTERSECTS WORK IN THIS CONTRACT, CONTRACTORS SHALL COORDINATE ALL WORK SO THAT COMPLETED WORK IS CONTINUOUS AND UNBROKEN. DIMENSIONS SHOWN FOR WORK BY OTHERS WITHIN OUTLINE OF TOWER, ARE FOR COORDINATION ONLY.
7. PROVIDE LOOSE LINTELS AS REQUIRED OVER ALL DUCT AND DUCT OPENINGS IN MASONRY PARTITIONS.
8. GLAZED FACE CONCRETE BLOCK MASONRY UNITS SHALL BE USED IN LIEU OF FACING TILE AS INDICATED ON PLANS. THE TOTAL THICKNESS OF GLAZED MASONRY UNITS SHALL BE EQUAL TO TOTAL THICKNESS OF FACING TILE PLUS BACKUP. BACK-UP.

SECTION (A/10) SCALE 1/4"=1'-0"

Note: SECTION (D/10) SAME AS OPPOSITE HAND EXCEPT AS NOTED ON PLAN AND ELEVATION AS SHOWN

SECTION (C/10) SCALE 1/4"=1'-0"

Note: SECTION (D/10) SAME AS OPPOSITE HAND EXCEPT AS NOTED ON PLAN AND ELEVATION AS SHOWN

PATH OFFICES

SECTION (D/10) SCALE 1/4"=1'-0"

Note: SECTION (C/10) SAME AS OPPOSITE HAND

OPERATING LEVEL OF REFRIGERATION RM. EL. 98'1.0"

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPILATION

CONTRACT	BID	DRAWING	date 2-1-68	
		1	1-30-70	A-66 LWL
		2	1-30-70	A-67 LWL
		3	5-23-69	A-28 DJL
		4	6-11-69	A-29 LWL
		5	1-15-70	A-15 ASH
		6	11-1-69	A-16 MJB
7-17-70	A-349	7	11-1-69	A-11 MW
1-19-70	A-211	8	4-15-68	A-65 RG
6-15-71	A-165	9	4-29-68	L-2 GD
11-6-70	A-16	10	5-15-70	LWL

DATE | SEQ. No. | BY | NO. | DATE | SEQ. No. | BY

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: SUB-LEVEL 3 FLOOR PLAN
ELEVATION 2'-4"-0"

DRAWN		CHECK	
SCALE	1/8"=1'-0"	DATE	7-31-70
PROJECT NUMBER		PAGE	66
DRAWING NUMBER	A-A-10		