PARKING

A.C. PLENUM

A.C. TRANSFER PLENUM

TENANT STORAGE
PAV. FL. EL. (274'-0")

UNOCCUPIED SPACE
ELEV. PIT ABOVE

ELEVATOR PIT

DUCT SPACE

PIPE SHAFT

A.C. SHAFT

STEAM SHAFT

CELLS

SUMP

A.C. FAN ROOM

ELEVATOR MACHINE ROOM

STAIR

ENTRANCE PLENUM

GLAZED BLOCK

NORTH

NOTES:

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULE, DOOR SCHEDULE AND SCHEDULE OF DRAWINGS SEE DWGS. P-A-1 TO P-A-4
2. FOR COMPLETE DIMENSIONS AND NOTES ON CORE AREA SEE "B" SCALE CORE DRAWING P-A-A2
3. ALL ELEVATIONS GIVEN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEER DRAWINGS.
5. FINISH FLOOR ELEVATION 6" TOP OF SLAB UNLESS OTHERWISE NOTED THUS (+0'-0 1/2") UNLESS STAIRWAY, ELEVATOR, CELL, ETC. INDICATED.
6. ALL WALLS AND PARTITIONS SHOWN WITH HATCHING ARE INCLUDED IN THIS CONTRACT. ALL WORK OUTSIDE PERIMETER, WALLS OF TOWER, SHOWN UNHATCHED IS IN A SEPARATE CONTRACT BY OTHERS. WHERE WORK BY OTHERS INTERFACES WORK IN THIS CONTRACT, CONTRACTOR'S SHALL COORDINATE ALL WORK, SO THAT COMPLETED WORK IS CONTINUOUS AND UNINTERRUPTED, UNLESS OTHERWISE SHOWN FOR WORK BY OTHERS OUTSIDE OF TOWER, SEE GEN. COORDINATION RULES.
7. EXPANSION JOINTS LOCATED AS SHOWN THUS (E.J.) ALL SAW CUT JOINTS SHALL BE ALIGNED WITH PARTITIONS.
8. GLAZED FACE CONCRETE BLOCK MASONRY WALLS TO BE USED AT LINE OF ENTRANCE TILE AS INDICATED ON PLANS. TYPE I TYPICAL THICKNESS 12" GLAZED ASSEMBLY 13 5/8" & 14" TYPE II TYPICAL THICKNESS AT ENTRANCE TILE PLAN ASSEMBLY 8 5/8" & 9" TYP.

UPPER PART OF PATH OFFICES

NOTE:
FOR CONTINUATION OF PLAN, DIMENSIONS AND DETAILS SEE "B" SCALE CONTRACT DWGS.

TENANT STORAGE

NOTE:
FOR CONTINUATION OF PLANS, DIMENSIONS AND DETAILS SEE "B" SCALE CONTRACT DWGS.

UPPER PART OF REFRIGERATION RM.
OPERATING LEVEL

NOTE:
FOR CONTINUATION OF PLAN, DETAILS AND DIMENSIONS SEE "B" SCALE CONTRACT DWGS.

BULLETINS NOT DATED ARE THE PROCESS OF CC 1/2 ON

CONTRACT NO. DRAWING dated 2-2-68

				2-15-68	A-75		A.M.
				1-30-68	A-44		C.J.
				1-30-68	A-47		L.H.
			A-376	L.J.	5-23-69	A-25	D.L.
4	9-6-73	A-554	L.B.	6	6-11-69	A-28	J.M.L.
3	7-17-73	A-549	L.J.	5	11-1-68	A-11	M.H.
2	8-1-72	A-565	L.C.	4	8-1-68	A-10	D.G.
1	1-28-71	A-211	L.C.	3	6-28-68	A-5	D.L.
0	6-18-71	A-183	D.T.	2	4-26-68	A-9	P.A.
A	11-6-70	A-19	L.J.	1	3-15-68		J.M.L.

DATE | NO. REC. BY | NO. DATE SUB. NO. BY

REVISIONS | REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — EMERY ROTH & SONS
MINORU YAMASAKI, ARCHITECT — RICHARD ROTH, ARCHITECT

WORTHINGTON SKILLING, HELLE & JACKE — JAROS, BAUM & BOLLES
STRUCTURAL ENGINEERS — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — THE PORT OF NEW YORK AUTHORITY
ELECTRICAL ENGINEERS — PAVING, UTILITIES, FOUNDATIONS

TITLE: SUB-LEVEL 1 FLOOR PLAN
ELEVATION 274'-0"

DRAWING | CHECKED BY
SCALE 1/8"=1'-0" | DATE 2-15-68
FILE NO. | NO. OF SHEETS | SHEET NO.

DRAWING NUMBER A-A-12