NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, CODES, SCHEDULES AND SCHEDULES OF DRAWINGS SEE DWG. A-1.00.
2. FOR COMPLETE 79th FLOOR PLAN SEE DRAWING # A-1.079.
3. ALL ELEVATIONS GIVEN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEER'S DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG. A-3.1-504 AND A-3.1-505.
6. ALL TRENCH GRADINGS TO BE PROTECTED AT UNGUARDED FLOOR AREA, 6 INCHES TO 8'-0" WITH A TEMPORARY TYPE BARRICADE. FOR ADDITIONAL CONDITIONS AND TYPE AND SIZE, CONSULT A CONTRACTOR APPROVED SHOP DRAWINGS FOR LOCATION & EXTENT OF FINISHED HEADERS, AND FRAMING.
7. FINISH FLOOR, ELEVATIONS AND TOP OF SLAB ELEVATIONS ARE GIVEN TO NEAREST DECIMAL OF METERS.
8. FINISH SOUND ENCLOSURES AT ALL PARTITIONS BOUNDING TOILETS, DUCT SHAFTS, F.E. DOOR CABINETS, ACCESS DOORS, TO SLAB ABOVE. ALL SUCH PARTITIONS SHALL BE CONSTRUCTED IN ACCORDANCE WITH TYPICAL DWG. AND TYPICAL DETAIL DWG. # A-3.1-501.
9. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS, STAIRS, PASSAGE ETC., BOTTOM OF CONCRETE SLAB, PIPING AND DUCTWORK SHALL BE PAINTED. PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF ALL OBSTRUCTIONS.
10. EXTENT OF PUBLIC CORRIDOR, CEILING IS INDICATED THUS:
11. COUNTS ARE MEASURED ON ALL SLAB PROJECTIONS OVER 12" (300mm) OR MORE, SHUTTER SLOPES SHALL BE CONSIDERED AS 45° TO THE HORIZONTAL. SEE TYPICAL DETAILS.
12. FOR DIMENSIONS AT JOINT STRADDLING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-3.1-502 TO A-3.1-510.

CONTRACT	BID DRAWING	date 5-1-68
5-1-72 A-1.07	L-J	5-13-70 A-75 A-A
12-27-72 A-1.00	L-C	1-30-70 A-82 T-J
A-1.06	L-C	1-30-70 A-83 T-J
6-15-71 A-1.76	L-J	1-30-70 A-87 L-J
4-15-71 A-1.64	D-T	5-15-69 A-81 Sect
A-1.76	L-J	5-15-69 A-86 Sect
4-15-71 A-1.64	D-T	5-15-69 A-17 Sect
6-15-71 A-1.64	D-T	5-15-69 A-85 Sect
6-15-71 A-1.65	D-T	5-1-68 A-10 DIG
11-6-70 A-1.00	L-J	5-20-68 A-5 DIG

REVISIONS

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH W. LORING & ASSOCIATES
SOILS & GEOLOGICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 79th FLOOR CORE PLAN
UPPER ESCALATOR LEVEL

DRAWING
SCALE 1/8"=1'-0"
PROJECT ENGINEER
DRAWN
CHECKED
DATE 7-30-68
SHEET OF

A-A-137