NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-A-1 TO A-A-6.
2. FOR COMPLETE 8" SCALE PLANS, PLAN SEE DRAWING A-A-144.
3. ALL ELEVATIONS GIVEN THUS (CH.0"-) ARE IN RELATION TO FINISH FLOORS.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DRAWINGS A-A-6-004 AND A-A-6-005.
6. ALL TRENCH GRATES TO BE RECESSED AT FACE/SIDE OF SLAB FOR A WIDTH OF 3/4" WITH A SPLASH-TYPE WATERPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TILE AND ELECTRICAL ENGINEERS AND CONTRACTORS APPROVED SHOP DRAWINGS FOR LOCATION AND FITTING OF TRENCH HEADS, AND TERMINATIONS.
7. FINISH FLOOR ELEVATION (F.F.E.) OF SLAB ELEVATIONS ARE (CH.0") UNLESS OTHERWISE SHOWN OR NOTED.
8. NON-ADA TOILET COMPARTMENTS AT ALL MEN AND WOMEN'S TOILETS AND DRESSING AT EACH CLEANING ACCESS CLOSET TO HAVE DOOR/DOOR VALANCE TO BE LOCATED IN ACCORDANCE WITH THIS DRAWING. SEE TYPICAL TOILET DETAILS A-A-6-010.
9. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR SHOWN IN CORE'S, CORE PARTITIONS, ETC. SECTION-ELEVATION OF ALL 7'-0" AND SHUTTERS SHALL BE MAINTAINED ABOVE STONE FINISHED FLOOR TO UNDER SIDE ALWAYS CEILING INSTALLATION AND ASSEMBLY OF FULL HEIGHT TOILETS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS
11. CANTS ARE MEASURED ON ALL BEAM PROJECTIONS OVER 6" NOMINAL (6" ACTUAL) DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 2" FROM ADJACENT "FL. TO FL." VERTICAL SURFACES.
12. FOR TREATMENT OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-A-6-006 TO A-A-6-008.

TENANT SPACE

ELEVATOR MACHINE ROOM

SECONDARY MOTOR R.R.

ELEVATOR PENTHOUSE

SECTION A/A-146

CORRIDOR

ELEV. LOBBY

MEN

WOMEN

SERVICE ROOM

POWDER ROOM

ELEVATOR MACHINE ROOM

CLOSET

STAIR

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT NO. DRAWING NOS. A-1-14

NO.	DATE	BUL. NO.	BY
4	6-18-71	A-174	LJL
3	4-8-71	A-164	DT
2	10-8-70	A-108	LJL
1	1-30-70	A-61	LJL

REVISIONS

NO.	DATE	BUL. NO.	BY
1	1-30-70	A-58	LJL
2	1-30-70	A-47	E.C.
3	3-23-69	A-31	L.S.
4	3-23-69	A-26	L.C.
5	3-23-69	A-17	L.C.
6	3-23-69	A-13	L.C.
7	1-1-68	A-11	MJR
8	5-1-67	A-10	DHS
9	4-25-67	A-9	DHS
10	3-15-67		JALL

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 66TH FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	1/16"	DATE	7-24-67
TRACED		LOCATION	
APPROVED			

A-A-146