NORTH

NOTE
DUCTWORK OVER CORRIDOR 308 TO BE INSULATED WITH 2" THICK FIBERGLASS BLANKET WITH FOIL FACING

CORRIDOR

ELEV. LOBBY

ELEVATOR MACHINE RM.

SERVICE ROOM

POWDER ROOM #1

POWDER ROOM #2

CLOSET

STAIR #1

STAIR #2

S.A.R.A. SHAFT

A.C. SHAFT

MEN

WOMEN

MAIL

STEAM SHAFT

TENANT SPACE

SECONDARY METER RM.

ELEVATOR MACHINE ROOM

ELEVATOR SHAFT

SECTION 4/181

COL. 701 & 801

COL. 803

COL. DETAILS
SCALE: 1/2"=1'-0"

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, DOOR SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWING A-0.1 TO A-0.5.
2. FOR COMPLETE "B" SCALE FLOOR PLAN SEE DRAWING A-B-101.
3. ALL ELEVATIONS GIVEN THUS 000'-0" ARE IN RELATION TO PROJECT DATUM.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWGS. A-B-004 AND A-B-005.
6. ALL TRENCH HEADERS TO BE FIREPROOFED AT WORKFACE OF SLAB FOR A WIDTH OF 6'-0" WITH A SPRAY-ON TYPE FIREPROOFING, SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEER AND CONTRACTOR'S APPROVED SHOP DRAWING FOR LOCATION AND EXTENT OF TRENCH HEADER AND ENCLOSURE.
7. FIN. FL. ELEV. ELEVATION AND TOP OF SLAB ELEVATIONS ARE TO BE ... UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE ... DISPENSERS AT ALL MEN AND WOMENS TOILETS.
9. DOOR ... FROM LAVATORY ACCESS DOORS TO STAIR ... IS LOCATED TO RECOMMENDATIONS WITH FILE NO. ... TO BE TAKEN FROM FLOOR TO TOP OF FINISH.
10. ALL ... SHALL COMPLY AND CONFORM TO ALL APPLICABLE CODES AND LAWS AND ORDERS, ETC., HAVING JURISDICTION. ALL ... SHALL BE SUBORDINATED TO SITE ABOVE FINISHED FLOOR TO PROVIDE HEADROOM CEILING INSTALLATION AND CLEARANCE OF ALL SUBJECT DOORS.
11. EXTENT OF PUBLIC CORRIDOR, CEILING IS INDICATED THUS: ...
12. CHUTES ARE ... ARRANGED SO ALL BEAM PROJECTIONS OVER 6'0" NOMINAL (6" ACTUAL) DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MAXIMUM OF ... FROM HORIZONTAL SEE TYPICAL DETAILS.
13. FOR PREFABRICATION OF FILM STRIPPING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-B-301 TO A-B-315.

BULLETINS NOT DATED ARE IN THEIR APPROPRIATE CONTRACT OR COMPLETION

CONTRACT	NO.	DRAWING	DATE	BY
			1-30-70	A-61	E.C.
			1-30-70	A-65	E.C.
			1-30-70	A-67	E.C.
			8-28-69	A-96	D.D.
			8-28-69	A-97	D.D.
			8-28-69	A-98	D.D.
			11-1-68	A-41	M.M.
A	6-18-71	A-134	L.J.	8-1-68	A-119	P.G.
A	6-18-71	A-154	D.T.	4-29-68	A-2	P.G.
A	7-1-71	A-133		- "68		J.V.L.

REVISIONS

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES MINORU YAMASAKI, ARCHITECT	EMERY ROTH & SONS RICHARD ROTH, ARCHITECT
WORTHINGTON, SKILLING, HELLE & JACKSON STRUCTURAL ENGINEERS	JAROS, BAUM & BOLLES MECHANICAL ENGINEERS
JOSEPH R. LORING & ASSOCIATES ELECTRICAL ENGINEERS	THE PORT OF NEW YORK AUTHORITY PAVING, UTILITIES, FOUNDATIONS

1/8"=1'-0"

TITLE: 95TH FLOOR CORE PLAN

DRAWN		TRACED	
SCALE	1/8"	DATE	7-16-71
PROJECT ENGINEER		CHECK	
SUBMITTED NUMBER		SHEET	OF

DRAWING NUMBER: A-A-151