NORTH

NOTES:

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FLOOR CONCRETES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS, SEE DRAWINGS "A-A-1-1 TO A-A-6.
2. FOR COMPLETE 96" SCALE FLOOR PLAN SEE DRAWING "A-A-156.
3. ALL ELEVATIONS GIVEN THUS (100'0") ARE IN ADDITION TO PORT AUTHORITY DATUM.
4. FOR MECHANICAL AND ELECTRICAL LEGENDS SEE ARCHITECTURAL ENGINEERS DRAWING.
5. FOR TYPICAL STAIR DETAILS SEE DRWGS "A-A-8-906 AND "A-A-8-910.
6. ALL TRENCH HEADERS TO BE WATERPROOFED AT UNDERSIDE OF SLAB AND A MINIMUM OF 6" INTO A SUITABLE CONCRETE WALL. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND SIZE. ENGINEERS & CONTRACTORS APPROVED SHOP DWG. SHOWING # SIZE OF TRENCH HEADERS AND PENETRATIONS.
7. FILLER PANEL ELEVATIONS & TOP OF SLAB DEPTHS AND OUTLETS SHOWN ON ARCHITECTURAL DRAWINGS ARE APPROX.
8. PLUMBING SHOP DRAWINGS OF ALL MEN AND WOMEN'S TOILETS, UNIT DISPENSERS, AS WELL AS LOCATIONS, ACCESS DOORS TO SHOW ENVIRONMENTAL PLANTS TO BE SUBMITTED TO THE CONSULTING ARCHITECTS, ENGINEERS AND THE PORT AUTHORITY FOR APPROVAL PRIOR TO ORDERING. ALL PLUMBING FIXTURES TO BE SELECTED FROM THOSE LISTED FOR THEIR USE IN HOSPITALS, STATE INSTITUTIONS ETC. BOTTOM CLEARANCE OF ALL PIPING AND EXTERNAL SURFACES SHALL BE DETERMINED AT 6'-0" ABOVE FINISHED FLOOR TO PROVIDE FOR MAXIMUM CLEANING FACILITY AND CLEARANCE OF MOP SINKS UNDER.
9. MATERIAL OF PUBLIC CORRIDOR, CEILING IS INDICATED THUS:
10. LIGHTS, ARE RECESSED, ON ALL DRAWN PERIMETER WALLS, 6" MINIMUM CLEARANCE BETWEEN FACE OF LIGHT FIXTURE AND WALL AND SHALL BE CENTERED TO FACE OF WINDOW MULLION. SEE TYPICAL DETAILS.
11. FOR ELEVATIONS, FINISHES AND COLORS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-A-8-105 TO A-A-8-112.

NOTE: 1 HANDICAP DUCT WORK NO. 2 SPRINKLER LINES TO BE METAL AS DETERMINED BY FIELD CONDITIONS PLASTIC AND TO BLEND WITH SURROUNDINGS

PART PLAN AT 100TH FLOOR

PART PLAN AT 100TH FLOOR

PART PLAN AT 100TH FLOOR

PART PLAN AT 100TH FLOOR

DELETIONS NOT DATED JAN. 11 THE PROCESS OF COMPLETION

CONTRACT BID DRAWING date 2-1-68

NO.	DATE	DWG. NO.	BY
1	11-74	A-315	J.P.
2	6-15-71	A-176	L.J.
3	6-15-71	A-170	L.J.
4	6-18-71	A-164	D.T.
5	7-1-71	A-157	T.T.

REVISIONS

NO.	DATE	DWG. NO.	BY
1	2-1-71	A-153	T.T.
2	3-5-71	A-151	E.C.
3	3-30-71	A-63	E.C.
4	3-30-72	A-67	E.C.
5	5-23-69	A-34	L.S.
6	5-23-69	A-96	L.S.
7	5-23-69	A-98	L.S.
8	5-23-69	A-93	L.S.
9	11-1-68	A-7	M.M.
10	2-1-68	A-60	C.G.

REVISIONS

REGISTERED ARCHITECT

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

WORTHINGTON, SKILLING, HELLE & GRACKSON
STRUCTURAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 96TH TO 100TH FL. CORE PLAN

DRAWN		CHECKED	
SCALE	1/8"=1'-0"	DATE	7-26-67
PROJECT		SHEET	OF
DRAWING NUMBER	A-A-157		