NORTH

NOTES:

1. FOR GENERAL NOTES, KEY TO MATERIAL, SYMBOL, ABBREVIATIONS PLOTS, SCHEDULES, DOOR, SCHEDULES AND SCHEDULES OF GRADING SEE DRAWINGS A-0.01 TO A-0.04
2. FOR MARKERS (1 SMALL FLOOR) PLAN SEE DRAWING A-0.0
3. ALL ELEVATION GIVEN THUS (100'0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LEGEND SEE ARCHITECTURAL DRAWINGS.
5. FOR TYPICAL TOILET ROOMS SEE DRAWINGS A-2.0-04 AND A-2.0-05.
6. UNLESS NOTED, ELEVATIONS OF TOP OF SLAB, ELEVATIONS ARE GIVEN ONLY TO FINISH SURFACE OF CONCRETE.
7. WHERE ACOUSTICAL CEILING IS CALLED FOR, SUCH AS IN CORRIDORS, STORE ROOMS, ETC., BOTTOM ELEVATION OF ALL PIPES AND DUCTWORK SHALL BE MAINTAINED AT 8'-2" MINIMUM ABOVE FINISHED FLOOR TO PROVIDE AN ADEQUATE HEADROOM AND CLEARANCE OF FULL HEIGHT DOORS.
8. CLEARANCE REQUIRED ON ALL BEAM PROJECTIONS OVER 6" MINIMUM (6" ACTUAL) DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MAXIMUM 18" FROM HORIZONTAL. SEE TYPICAL DETAILS.
9. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-2.0-02 TO A-2.0-03.

DUCT SHAFT

DUCT PIPE AND CORD SHAFT

DUCT AND CORD SHAFT

DUCT SHAFT

BALCONY

BALCONY

BULLETINS, NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT	BID	DRAWING	date 12-9-68
		1-20-70	A-47
		5-21-69	A-32
11-16-74	A-253	8-23-69	A-26
12-16-75	A-272	12-19-69	A-17
10-3-73	A-248	2-1-69	A-17
6-28-67	A-182	2-1-68	A-13
6-2-76	A-264	8-1-68	A-10
6-1-71	A-123	6-28-68	A-6
11-6-70	A-108	5-22-68	A-5
5-15-70	A-75	3-18-68	

NO. DATE SUB. NO. BY — REVISIONS

NO. DATE SUB. NO. BY — REVISIONS

APPROVED

CHIEF, PLANNING DIVISION — DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT

SUPERSTRUCTURE, CEILING, WALLS & PARTITIONS; STRUCTURAL ENGINEERS

SEVERUD, BANDI, ERICKSON — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY, PAVING, UTILITIES, FOUNDATIONS

TITLE: 2ND FLOOR CORE PLAN

ELEVATION 33'0"

PLAN LEVEL

SCALE: 1/16" = 1'-0"

PROJECT NUMBER

DRAWING NUMBER: A-A-22