NORTH

NOTES

1. FOR GENERAL NOTES KEY TO NOTE NO.'S SYMBOLS ABBREVIATIONS FLOOR NUMBERS AREA NUMBERS AND NOTATIONS OF DRAWINGS SEE DRAWING S-A-1 TO S-A-5
2. FOR COMPLETE "E" SERIES PLANS SEE DRAWING E-A-31
3. ALL DIMENSIONS GIVEN THUS (10'-0"-) ARE IN RELATION TO FINISH FLOORS.
4. FOR MECHANICAL AND ELECTRICAL LEGENDS SEE DRAWING SHEET NOS.
5. FOR TYPICAL STAIR DETAILS SEE DWG.# A-A-5-106 AND A-A-5-206
6. FINISH FLOOR ELEVATION (10'-0") TOP OF SLAB ELEVATION (10'-0") UNLESS OTHERWISE SHOWN OR NOTED.
7. WHERE NO SUSPENDED CEILING IS CALLED FOR, SUCH AS IN TOILETS, STAIRS, MATERIALS ETC., BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE PAINTED AT 8'-0" ABOVE FINISHED FLOOR, TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOOR.
8. JOINTS ARE ARRANGED ON ALL SLAB PROJECTIONS OVER 24" (GENERAL (E-ASTRAL) DIMENSION H ELEVATION, T-JOINTS AND SHALL BE MINIMUM 75° FROM HORIZONTAL SEE TYPICAL DETAILS.
9. FOR TOILET PARTITION DETAILS SEE DRAWINGS A-AB-106 TO A-AB-116
10. ELEVATION TO TOP OF ALL CONCRETE CURBS TO BE (10'-0") UNLESS OTHERWISE SHOWN OR NOTED

NOTES

1. SMOKE-LESS INTERRUPTION AT TOP OF SLAB WITH 3" CURB.
2. TYPE OF ASPHALTIC INTERRUPTION TO LOOK AS ALL CROSS SEE TYPICAL DETAILS ON DWG.# A-A-5-211 (A-A-5-201)
3. FOR DEPTH OF CONC. FOOD FOR ASPHALTIC PAVEMENT SEE DWG. # A-A-5-106
4. FOR FINAL SIZE & LOCATION OF CONCRETE PADS SEE P.A.N.Y.C. & PLUMBING CONTRACTOR'S DRAWINGS.
5. REMOVE FLOOR, CEILING SUPPORTS ALL PIPE & DUCT OPENINGS IN PARTITIONS SEE DETAILS A-A-5-106
6. WHERE FINISHED FLOOR IS RAISED ABOVE (10'-0"), FLOOR SHALL BE 3/4" CEMENT FINISH OVER AND DENSITY FILLED FROM SLAB.
7. PROVIDE 2" RIGID INSULATION AT UNDERSIDE OF MECHANICAL EQUIPMENT ROOM FLOOR.

COLUMN DETAILS

Col. #702 & #707

Col. #705

Col. #802 & #806

Col. #805

CONTRACT NO.	DRAWING - date 6-9-68
A 1-69-76 A-201 L-1	A 1-20-70 A-47 L-1
A 1-71 A-267 L-1	A 2-24-69 A-17 L-1
A 1-76-76 A-199 L-1	A 2-24-69 A-17 L-1
A 1-70-71 A-222 L-1	A 2-25-69 A-23 L-1
A 6-8-71 A-184 L-1	A 1-21-69 A-17 L-1
A 1-8-70 A-108 L-1	A 1-21-69 A-98 L-1
A 2-8-70 A-85 L-1	A 11-1-68 A-8 L-1
A 2-8-70 A-79 L-1	A 6-1-68 A-10 L-1
A 2-8-70 A-89 L-1	A 6-23-6-8 A-6 L-1
A 2-8-70 A-89 L-1	A 6-6-68 L-1

DATE - REVISION NO. - BY

REVISIONS

BULLETINS NOT LISTED ARE IN THE PREPARATION OR CONSTRUCTION

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
LIGHTING CONSULTANTS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
ARCHS. UTILITIES/FOUNDATIONS

TITLE: 7TH FLOOR CORE PLAN
LOWER MECH EQUIP ROOM LEVEL

SCALE	1/16" = 1'-0"	DRAWN	
DATE	6-9-68	CHECKED	

A-A-32