NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO SYMBOLS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF MULLIONS SEE DRAWINGS A-A-1 TO A-A-5.
2. FOR COMPLETE 1/8" SCALE FLOOR PLAN SEE DRAWING A-A-87.
3. ALL ELEVATIONS GIVEN THUS (CH-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STUD DETAILS SEE DWG. A-A-A-A-806 AND A-A-A-808.
6. ALL TRENCH HEADERS TO BE PROVIDED AT UNDERSIDE OF SLAB FOR A WIDTH OF 6'-0" WITH A SPRAY-ON TYPE FIREPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE OF ELECTRICAL ENGINEERS AND CONTRACTORS APPROVED SHOP DRAWINGS FOR LOCATION AND EXTENT OF TRENCH HEADER AND FIREPROOFING.
7. FINISH FLOOR ELEVATION 2" TOP OF SLAB ELSEWHERE UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSER IN MEN AND WOMENS TOILETS, ONE DISPENSER AT EACH LAVATORY, RECESS UNDER TILE COUNTER, VALVE TO BE LOCATED IN ACCORDANCE WITH TILE COUPONS. SEE TYPICAL TOILET DETAILS, DRAWING A-A-A-806.
9. WATER, HOT DISPOSAL CONNECTIONS, DRAIN ETC. IN TOILETS, STAIR PASSAGE ETC., BOTTOM ELEVATION OF ALL PIPES AND DUCTWORK SHALL BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR, TO PERMIT OF SUSPENDED CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: ——— ——
11. CARTONS ARE ASSUMED ON ALL BEAM PROJECTIONS OVER 6", NOMINAL (ACTUAL) DIMENSIONS IN ELEVATOR SHAFTS ARE SHOWN TO FACE OF FURRING. SEE TYPICAL DETAILS.
12. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-A-A-806 TO A-A-A-812.

PART PLAN AT 16TH FLOOR

DETAILS OF PACKAGED 1½ HR. LINE FIRE THRU WIN.

PART PLAN AT 16TH FLOOR

ELEVATION OF SHELVING IN U.S. MAIL VAN LOCKS

SECTION A-A

CONTRACT	BID	DRAWING	date 2-9-66
	7-10-70	A-17	L-4
	1-20-70	A-81	L-
	1-20-70	A-86	L-
	1-20-70	A-87	L-
11-15-74	A-595	J.R.	9-21-71	A-81	ATS
12-17-71	A-300	J.C.	8-29-67	A-86	S.S.
6-8-71	A-738	BEL.	8-29-67	A-17	mech
8-27-71	A-174	DT	8-29-67	A-15	mech
9-7-71	A-163	L.J.	11-1968	A-7	MM
11-1-70	A-165	L.J.	8-1-68	A-10	DG

NO.	DATE	REVISIONS	BY

NO.	DATE	REVISIONS	BY

APPROVED

CHIEF, PLANNING DIVISION (TC)

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY — PAVING, UTILITIES, DRAINAGE

11TH TO 16TH FL. CORE PLAN

SCALE 1/8" = 1'-0"

DESIGN

DRAWN

PROJECT

CHECKED

DATE 7-10-70

CONTRACT

DRAWING A-A-A-395