NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND DIAGRAMS OF COLUMNS SEE DRAWINGS A-A-1 TO A-A-8.
2. FOR COMPLETE 21 BOARD FLOOR PLAN SEE DRAWING A-A-79.
3. ALL ELEVATIONS GIVEN THUS (+0.0) ARE IN RELATION TO TYPICAL FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LEGENDS SEE RESPECTIVE DIAGRAMS.
5. FOR TYPICAL STAIR DETAILS SEE DWG. A-A-301 AND A-A-302.
6. ALL PLANTER HEADERS TO BE PLASTERBOARD AT HORIZONTAL OF SLAB FOR, 4 METAL BY 4" WITH A SPACER OF TYPE OF FILLER BOARD SEE ARCHITECTURAL SPECIFICATIONS FOR TYPES & MATERIAL DRAWINGS & CONSTRUCTION DETAILS AND SHEET FOR, LOCATION & EXTENT OF PLANTER HEADERS & FILLER BOARDS.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE REFERRED TO DATUM ESTABLISHED ON SHT. NO. A-A-1.
8. FLOOR SLAB DEPRESSIONS FROM ADJACENT FINISHED FLOOR, AS INDICATED AT EACH LAVATORY, ASSUME CHANGE IN SLAB THICKNESS TO BE 1" UNLESS OTHERWISE NOTED ON DRAWINGS. SEE TYPICAL TOILET ROOMS A-A-201 & 202.
9. DOUBLE RIB SUSPENDED CEILINGS, AS AT CLOSED FOR, 2 INCH AS IN CORRIDORS, UTILITY SPACES ETC., BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK, SHALL BE MAINTAINED AT 8'-0" ABOVE FINISHED FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS
11. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 3½" MINIMUM (4" ACTUAL) PROJECTION IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 1½" FROM HORIZONTAL. SEE TYPICAL DETAILS.
12. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-A-306 TO A-A-316.

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT NO.	DRAWING	Bulletin No.	
	1-30-70	A-87	EC
	2-13-70	A-13	EC
	9-15-69	A-81	KTH
	5-13-69	A-84	EC
	5-15-69	A-17	EC
	2-19-69	A-23	EC
6-18-71	A-46	BBL	
8-15-70	A-78	LH	
4-30-70	A-81	LH	
1-30-70	A-83	LH	

NO.	DATE	BULL. NO.	BY
REVISIONS			

NO.	DATE	BULL. NO.	BY
1	11-1-68	A-11	HM
2	8-1-69	A-10	EC
3	12-23-69	A-83	EC
4	2-19-70	A-87	EC
REVISIONS			

REGISTERED ARCHITECT MINORU YAMASAKI

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PIERS, UTILITIES, FOUNDATIONS

TITLE: 47TH FLOOR CORE PLAN

½"=1'-0"

DRAWN		TOP SHEET	1
SCALE	1/8"=1'-0"	DATE	10-1-69
PROJECT NUMBER		SHEET	OF
DRAWING NO.	A-A-79		