NORTH

NOTES:

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-0.1 TO A-0.4.
2. FOR COMPLETE 8" SCALE, MODEL PLAN SEE DRAWING A-0.80
3. ALL ELEVATIONS GIVEN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LEGENDS, SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWGS. A-0.206 AND A-0.205.
6. ALL TRENCH HEADERS TO BE RE-EMPLOYED AT UNDERSIDE OF SLAB FOR A WIDTH OF 6'-0" WITH A REPLACEMENT TYPE OF FINISH COVERING SEE FINISH SCHEDULES FOR TYPE. ELECTRICAL ENGINEERS & CONTRACTORS EMPLOYED SHOULD CHECK LOCATION & EXTENT OF TRENCH HEADERS & RE-EMPLOYMENT.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (+0'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. SECURITY DOOR CONTROLLERS IN ADJACENT TOILETS, DWG SUPERVISED AT EACH SANITARY ACCESS DOOR TO BUILDING TOILETS TO BE LOCATED IN MECHANICAL EQUIPMENT TYPE TOILETS, SEE PARTICULAR FINISH DETAILS DRAWING A-0.205-FIN.
9. WHERE OR SUSPENDED CEILINGS ARE CALLED FOR, SHOP AS IN CORRIDORS, DUCTS, PIPESPACES ETC., SECTION ELEVATION OF ALL PIPES AND DUCTWORK SHALL BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR TO PROVIDE ADEQUATE CEILING INSTALLATION AND CLEARANCE FOR SUSPENDED CEILINGS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: ——————
11. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 3½" MINIMUM (4" NOMINAL) DIMENSION IN ELEVATION. CANTS ALSO SHALL BE PROVIDED AT ALL PANEL AREAS OVER 4 SQ. FT. SEE TYPICAL DETAILS.
12. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-A0.206 TO A-A0.212

COL. 901 — COL. 908

COL. 905 — COL. 902 & 907

COLUMN DETAILS
SCALE ½"=1'-0"

NOTE: FOR DETAILS DIMENSIONS FINISHES & SLABS SEE A-A0.BASE 203 ELEVATION LOBBY DETAILS DWGS. A-A 1.3-210

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT	BID	DRAWING	date 5-1-68		
		1	1-20-70	A-81	L.H.
		2	1-30-70	A-82	L.H.
		3	1-30-70	A-83	L.H.
		4	5-29-69	A-0	R.C.
		5	5-29-69	A-31	R.L.
1	5-29-70	A-176	L.H.	5-22-69	A-1.6	R.L.
2		A-1.65	L.H.	5-27-69	A-17	R.L.
3	6-18-71	A-164	R.R.L.	5-22-69	A-2.3	R.L.
4	11-6-70	A-109	L.H.	5-4-68	A-110	D.G.
5	5-28-70	A-78	R.L.	5-22-68	A-1.5	D.G.

REVISIONS

REVISIONS

APPROVED:

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES MINORU YAMASAKI, ARCHITECT	EMERY ROTH & SONS RICHARD ROTH, ARCHITECT
WORTHINGTON, SKILLING, HELLE & JACKSON STRUCTURAL ENGINEERS	JAROS, BAUM & BOLLES MECHANICAL ENGINEERS
JOSEPH R. LORING & ASSOCIATES ELECTRICAL ENGINEERS	THE PORT OF NEW YORK AUTHORITY PAVING, UTILITIES & DRAINAGE

TITLE: 40TH FLOOR CORE PLAN

DRAWN		DESIGNED	
SCALE	1/8"=1'-0"	DATE	7-21-67
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER			A-A-81