NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SIMILAR INFORMATION SEE DRAWINGS "A-1.1 TO A-1.6"
2. FOR COMPLETE 'B' SCALE FLOOR PLAN SEE DRAWING "A-A-97"
3. ALL ELEVATIONS GIVEN THUS (62'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG [illegible]
6. ALL TRENCH HEADERS TO BE FURNISHED AT UNDERSIDE OF SLAB FOR A WIDTH OF 6'-0" WITH A DEPTH OF 1'-0" TYPE OF FURNISHINGS BY ARCHITECTURAL SPECIFICATIONS FOR TYPE & ELECTRICAL ENGINEERS & CONTRACTORS APPLIANCE SHOP DWGS FOR LOCATION & EXTENT OF TRENCH HEADERS & FURNISHINGS.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (62'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS ONE DISPOSES ITEM - LAVATORY. ALSO SHOWN TO BE LOCATED IN ACCORDANCE WITH THE LAYOUTS FOR TYPICAL TOILET DETAILS DWG "A-A-98-99"
9. WHERE TO SUSPENDED CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS STAIR LANDINGS ETC, BOTTOM ELEVATION OF ALL PIPING AND ELECTRICAL SHALL BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR, TO PERMIT FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR. CEILING IS INDICATED THUS [illegible]
11. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 6" MINIMUM, (6" ATTAIN) DIMENSION IN ELEVATOR SHAFTS AND SLABS TO MAINTAIN 90° FROM HORIZONTAL SEE TYPICAL DETAILS.
12. FOR FIRESTOPPING OF FIRE STAIRWELL COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-A-8-9-4 TO A-A-8-9-6.

BUILDING NOT DETAILED ARE IN THE PROCESS OF CONSTRUCTION.

CONTRACT NO. DRAWING date 6-1-68

NO.	DATE	DESCRIPTION	DRAWING	BY
			5-10-70	A-19	AM
			7-30-70	A-21	AS
			7-30-70	A-23	LJ
			7-30-70	A-27	LJ
			5-31-71	A-31	MM
			5-25-71	A-25	MM
			5-31-71	A-17	MM
1	2-22-72	A 238	5-25-71	A-33	MM
2	5-26-72	A-178	6-1-68	A-10	DG
3	6-8-72	A-184	7-17-68	A-2	DG

REVISIONS

NO.	DATE	DESCRIPTION	DRAWING	BY

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY — PAVING, UTILITIES, FOUNDATIONS

TITLE: 62nd FLOOR CORE PLAN

SCALE: 1/16" = 1'-0" — DATE: 7-30-69

PROJECT NUMBER:

DRAWING NUMBER: A-A-98