FileJuicer

FOR CONTINUATION SEE DWG. # E-A-91

FOR CONTINUATION SEE DWG. # E-A-89

NOTES:

1. FOR EMERGENCY POWER CENTER LAYOUT DETAILS SEE DWG. # E-A-99.
2. FOR MOTOR CONTROL CENTER SCHEDULES SEE DWG E-A-104 - 106.
3. FOR LIGHTING AND/OR RECEPTACLE PANEL SCHEDULES SEE DWG. E-A-109-114.
4. FOR EMERGENCY PANEL SCHEDULES SEE DWG # E-A-115.
5. FOR AUTOMATIC TRANSFER SWITCH SCHEDULE SEE DWG # E-A-99.
6. ALL PULL BOXES ARE NOT SHOWN. FOR LOCATION OF ADDITIONAL PULL BOXES SEE 1/8" SCALE FLOOR PLANS E-A-19 - E-A-32.
7. FOR TEMPORARY AND PERMANENT FACILITIES REQUIRED FOR CONSTRUCTION POWER SEE TEMPORARY LIGHT & POWER, RISER DIAGRAMS AND SERVICE DISTRIBUTION ON DWGS # E-A-132 THRU E-A-135 & E-X-1 & E-X-2.
8. FOR ELEVATOR DISTRIBUTION PANEL SCHEDULES SEE DWG. # E-A-100.
9. FOR FIRE COMMUNICATION SYSTEMS RISER DIAGRAM SEE DWG # E-A-95.
10. FOR EMERGENCY CONTROL RISER DIAGRAM SEE DWG # E-X-11.
11. FOR ELECTRIC CLOSET DETAIL SEE DWG # E-A-83 THRU E-A-86.
12. FOR EMERGENCY SINGLE LINE DIAGRAM SEE DWG # E-X-10.
13. FOR SUBSTATION SWITCHBOARD SCHEDULES SEE DWG # E-A-75 & E-A-76.
14. FOR PODS EMANATING FROM WATER SUPPLY PUMP CONTROL PANEL SEE DWG # E-A-25.
15. ALL CENTER ELECTRIC CLOSETS (CLOSETS "C") WILL CONTAIN 4-4" THROUGH THE WALL SLEEVES (BUSHED & CAPPED BOTH ENDS) INTO HUNG CEILING. ⚠1

CONTRACT BID DRAWING date OCT. 16, 1967

NO.	DATE	BUL. NO.	BY	NO.	DATE	BUL. NO.	BY
⚠1	12-18-67						

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: LIGHT AND POWER RISER DIAGRAM 25TH - 58TH FLOORS

DRAWN	R.F.H.	CHECKED	J.R.L.
SCALE	NONE	DATE	OCT. 16, 1967
PROJECT NUMBER		SHEET	77 OF 114
DRAWING NUMBER	E-A-90		