FileJuicer

FOR CONTINUATION SEE DRAWING # E-A-96

NOTES

1. RUN CONCEALED TO ELEVATOR MACHINE ROOM. FIRE CONTINUATION SEE FLOOR PLANS.
2. RUN CONCEALED TO SECONDARY MOTOR ROOM. FOR CONTINUATION SEE FLOOR PLANS.
3. AT THE OPTION OF THE CONTRACTOR, CLOSED CONDUITS FOR STAIR LIGHTING MAY BE RUN BETWEEN EXIT LIGHT OUTLET BOXES IN LIEU OF STAIR LIGHT OUTLET BOX.
4. ALL EXIT LIGHTS SHALL BE ON SEPARATE CIRCUITS, COMPLETELY INDEPENDENT FROM STAIR LIGHTING CIRCUITS.
5. RUN CONCEALED TO JUNCTION BOX IN HUNG CEILING FOR ESCALATOR EMERGENCY LIGHTING. FOR CONTINUATION SEE FLOOR PLANS.
6. FOR EMERGENCY RECEPTACLE PANEL SCHEDULES SEE DWG. E-A-115.
7. FOR FEEDER SIZES SERVING EMERGENCY RECEPTACLE PANELS SEE LIGHT & POWER RISER DIAGRAMS DWG. E-A-89 THRU E-A-92.

FOR CONTINUATION SEE DRAWING # E-A-94

CONTRACT BID DRAWING date OCT. 16, 1967

NO.	DATE	SUB. NO.	BY	NO.	DATE	SUB. NO.	BY
REVISIONS				REVISIONS			

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: EMERG. LT'G AND RECEPT. RISER DIAGRAM 25TH - 58TH FLOORS

DRAWN	R.F.H.	CHECKED	J.R.L.
SCALE	NONE	DATE	OCT. 16, 1967
PROJECT NUMBER		SHEET	81 OF 114
DRAWING NUMBER	E-A-95		