NOTES:
1- FOR GENERAL NOTES, KEY TO MATERIALS, FINISH SCHEDULE, DOOR SCHEDULE AND SCHEDULE OF DRAWINGS SEE DRAWINGS A.0-1 TO A.0-4.
2- FOR GRANITE'S, GLASS FLOOR, PLANTS SEE DRAWINGS A.0-16 TO A.0-19
3- ALL ELEVATIONS GIVEN THUS (0'-0") ARE TAKEN IN RELATION TO FINISH FLOOR, WHICH IS ELEVATION 100'-0"
4- FOR ALL MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DWGS.
5- FOR TYPICAL STAIR DETAILS AND SECTIONS SEE DRAWINGS A.2-1 & 5
6- FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATION ARE (0'-0") UNLESS OTHERWISE SHOWN OR NOTED.
7- CLOSETS ARE ASSUMED ON ALL BEAM PROJECTIONS OVER 6" ACTUAL DIMENSION IN ELEVATOR, SHAFTS AND SHALL BE MINIMUM 78" FINISH HORIZONTAL. SEE TYPICAL DETAILS.
8- FOR EXITS AND SUB-DIVISIONS OF TENANT SPACE SEE TENANT ARCHITECTS DRAWINGS.
9- ALL PARTITIONS SHOWN UNFINISHED ARE NOT INCLUDED IN THIS CONTRACT.
10- PROVIDE IRON LADDERS TO SPRINKLER CONTROL VALVES. SEE SPRINKLER DWG'S FOR LOCATION.
11- PROVIDE LINTELS OVER ALL DUCTS PASSING THRU MASONRY WALLS (SEE MECH DWGS)
12- FIRESTOP DUCTS BETWEEN TENANCIES WITH 2-SEPARATE LAYERS METAL LATH & 1" VERMICULITE PLASTER HARD TO DUCTS. FOR EXTENT OF FIREPROOFING, SEE MECHANICAL DRAWINGS.

North

Tenant Space
Tenant Space
A.C. Shaft #1
A.C. Shaft #2
Vesey Street Lobby
Pull Chamber
Tenant Space
Tel. Cl. E
Elec. Cl. E
Tel. Cl. F
Elec. Cl. F
Electric Distribution Room #1
Closet
Stair #3
Stair #4
Service Lobby
K.E. Fluc #2
Shaft #4
Sec #1
Sec #2
Sec #3
Jan. Cl. #1
Elevator Lobby
Mail Room
Escalator E-4
Escalator E-3
Tel. Corridor
Corridor
Building Directory
Tel. Corridor
Ramp Slab On From (-0'-8") To (-1'-8")
Tenant Space
East Core
Stair #2
Upper Part of Stair #3
Upper Part of Service Lobby
Upper Part of Closet
Upper Part of Tel. Cl. G
Upper Part of Elec. Cl. G
Pipe Shaft
Part Plan of Stairs #3 & #4 at Intermediate Level

RECEIVED
DEC 2 8 1990
LESLIE E. ROBERTSON ASSOCIATES
211 EAST 46th ST., N.Y.C. 10017

Bulletins not dated are in the process of completion

No.	Date	Bul. No.	By
4	8-13-76	E-127	DB
3	9-27-78	E-148	LWL
2	7-18-78	E-139	DB
1	7-18-78	E-138	DB
6	4-26-78	E-118	LWL
5	2-6-78	E-99	LW
4	2-6-78	E-107	LW
3	5-11-72	E-113	LC
2	5-7-71	E-3	LW

Revisions

No.	Date	Bul. No.	By
8	12-7-71	E-68	LWL
7	1-18-72	E-69	LWL
6	3-6-72	E-75	LWL
5	7-26-72	E-6	AM
4	7-26-72	E-8	AM
3	7-26-72	E-9	AM
2	8-22-72	E-10	DG
1	4-16-73	E-7	DG
1	11-29-89	E-1	DG

Revisions

Contract Bid Drawing dated 8-25-69

Approved
Chief, Planning Division
Date

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

Minoru Yamasaki & Associates
Minoru Yamasaki, Architect
Worthington, Skilling, Helle & Jackson
Structural Engineers
Joseph R. Loring & Associates
Electrical Engineers
Emery Roth & Sons
Richard Roth, Architect
Jaros, Baum & Bolles
Mechanical Engineers
The Port of New York Authority
Paving Utilities, Foundations

Title: Northeast Plaza Building
El 310 Core Plan

Drawn	R.T.H.	Checked	
Scale	1/4"=1'-0"	Date	7-20-67
Project Number		Sheet	of
Drawing Number	A-E-90		

1/4"=1'-0" 0 1 2 3 4 8 12