FINISH SCHEDULE

FLOOR	LOCATION / SPACE	FLOOR FINISH	BASE	WALLS MATERIAL	WALLS FINISH	CEILING MATERIAL	CEILING FINISH	REMARKS
		Vinyl Asbestos Tile; Vinyl Tile; Ceramic Tile; Marble; Terrazzo; Carpeting; Quarry Tile	Cement; Resilient; Ceramic Tile; Marble; Terrazzo; Quarry Tile; Wood; None	Masonry or Concrete; Concrete; Metal Stud; Facing Tile; Brick; Marble; Wood; Metal Lath & Plaster; Plaster	Unfinished; Paint, Covering; Wood; Ceramic Tile; Cim Plating; Facing Tile; Fire Brick; Spark Glass	Metal Pan; Acoustical Tile; Concrete; Steel Deck; Gyp Wallboard; Gyp Plaster; Luminous Ceil.	Painted; Unfinished	
47th FLOOR	ELEV. LOBBY							1. SEE TENANT ARCHITECTS DWG. FOR SUB-DIVISION OF SPACE AND FINISHES.
	TENANT SPACE							
	BUILDING CLOSET							
	CLOSET							
	CORRIDOR							
	STAIRS *1,*2,*3,*4,*5,*6							
	POWDER RM.*1,*2							
	VEST. *1,*2							
	TEL. CL. A,B,C,D,E,F,G,H,J,K							
	ELEC. CL. A,B,C,D,E,F,G							
	MEN *1,*2							
	WOMEN *1,*2							
	JAN. CL.							
	SERVICE LOBBY							
	LOBBY							
8th FLOOR	ELEV. LOBBY							4. SEE TENANT ARCHITECTS DRAWINGS FOR SUB-DIVISION OF SPACE AND FINISHES.
	CORRIDOR							
	TENANT SPACE							
	STAIRS *1,*2,*3,*4,*5,*6							
	POWDER RM. #1 & #2							
	VEST. *1,*2							
	WOMEN *1,*2							
	MEN *1,*2							
	SERVICE LOBBY							
	TEL. CL. A,B,C,D,E,F,G,H,J,K							
	ELEC. CL. A,B,C,D,E,F,G							
	CLOSETS							
	JAN. CL.							
	LOBBY							
	BUILDING CLOSET							
6th, 7th & 8th FLOORS	ELEV. LOBBY							5. SEE TENANT ARCHITECTS DRAWINGS FOR SUB-DIVISION OF SPACE AND FINISHES.
	TENANT SPACE							
	CORRIDOR							
	STAIRS *1,*2,*3,*4,*5,*6							
	MEN *1,*2							
	WOMEN *1,*2							
	VEST. *1,*2							
	POWDER RM.*1,*2							
	TEL. CL. A,B,C,D,E,F,G,H,J,K							
	ELEC. CL. A,B,C,D,E,F,G							
	JAN. CL.							
	SERVICE LOBBY							
5th FLOOR	ELEV. LOBBY							6. SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING. 7. SEE TENANT ARCHITECTS DRAWINGS FOR SUB-DIVISION OF SPACE AND FINISHES.
	SERVICE LOBBY							
	MECH. EQUIP. RM.							
	TENANT SPACE							
	STAIRS *1,*2,*4,*5,*6							
	STAIR VEST. *1							
	MEN *1,*2							
	WOMEN *1,*2							
	POWDER RM. *1,*2							
	VEST. *1,*2							
	M.E.R. VEST. *1,*2,*3							
	TEL. CL. 'C', 'D', 'H', 'K'							
	ELEC. CL. 'B', 'E', 'G'							
	A.C. PLENUM							
	CLOSET							
	CORRIDOR							
	MAINTENANCE PASSAGE							
	Unif. Cl.							
MAIN ROOF & BULKHEAD	ELEV. MACH. RM. (P.E.*1 THRU P.E.*6)							8. SEE ARCHITECTURAL PLANS FOR SOUNDPROOFING. 9. SEE TENANT ARCHITECTS DRAWINGS FOR SUB-DIVISION OF SPACE AND FINISHES.
	ELEV. MACH. RM. (S.E.*1 & S.E.*2)							
	STAIR *6							
	VEST. *1,*2							
	UNASSIGNED SPACE							

GENERAL NOTES

1. ALL DIMENSIONS ON DWGS. A.E-1 TO A.E-6 ARE TO ROUGH WALLS AND PARTITIONS. ALL DIMENSIONS ON DWG. A.E-101 TO A.E-158 ARE GIVEN TO FINISH UNLESS OTHERWISE SHOWN OR NOTED.
2. FOR WINDOW HEIGHTS SEE ELEVATIONS AND DETAILS. WINDOW HEIGHTS ARE NOMINAL. FOR ACTUAL DIMENSIONS SEE WINDOW CONTRACTORS DETAILS AND ERECTION DRAWINGS.
3. ALL DOORS WITH CLOSERS (OTHER THAN SPRING HINGE) TO BE KEPT 6" MINIMUM CLEAR OF ROUND WALLS ON HINGE SIDE.
4. CLEATS REQUIRED ON ALL BEAM PROJECTIONS OVER 2½" NOMINAL (ACTUAL) DIMENSION IN VENTOR UNITS AND SHALL BE MINIMUM 12" FROM FINISHED FULL SIZE TYPICAL DRAWING.
5. FOR CERTIFIED A.C. UNITS AIR CONDITIONING DUCT WORK, PIPING & EQUIPMENT SEE FOR TENANTS SPECS. ETC. SEE MECHANICAL DWGS.
6. FOR ALL PLUMBING PIPING, RISERS, DRAINAGE AND DETAILS ETC. SEE PLUMBING DWGS.
7. FOR ALL ELECTRICAL WIRING, RISER DIAGRAMS, LIGHTING, CONVENIENCE OUTLETS AND DETAILS ETC. SEE ELECTRICAL DWGS.
8. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 1'-0" WITH 3" SPRAY ON FIREPROOFING. SEE ARCHITECTURAL SPECIFICATION FOR TYPE AND THICKNESS. ARCHITECTURAL, ENGINEERS AND CONTRACTORS APPROVED SHOP DRAWINGS FOR LOCATION AND EXTENT TO BE GIVEN TO TRADES INVOLVED FOR FIREPROOFING.
9. WHERE AN SUSPENDED CEILING IS CALLED FOR, SUCH AS IN CLOSETS, STAIR, TOILETS ETC. THE FURRING FURNISHED AT ALL PLUMBING AND DUCT WORK SHALL BE SUFFICIENT AT ALL TIMES TO EXTEND FROM FLOOR TO UNDERSIDE OF SUSPENDED CEILING AND PROVIDING FOR FUTURE INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. WHERE CLIENT'S BLOCK FIREPROOFING IS CALLED FOR GROUND COLUMNS CINDER BLOCK IS SOLID BLOCK UNLESS OTHERWISE NOTED.
11. ALL ELECTRIC CELLS (POWER AND TELEPHONE) THAT ARE ENCASED OVER ELEVATOR, MACHINE ROOMS, SHAFTS AND STAIRS ARE TO BE FIREPROOFED AT UNDERSIDE FOR A WIDTH OF 4'-0" WITH A 3" SPRAY ON FIREPROOFING. SEE ARCHITECTURAL SPECIFICATION FOR TYPE AND THICKNESS. ELECTRICAL ENGINEERS AND CONTRACTORS APPROVED SHOP DRAWINGS FOR LOCATION AND EXTENT OF ELECTRIC CELLS AND FIREPROOFING.
12. ALL SLABS OUTSIDE OF BUILDING PERIMETER AT STREET LEVEL SHALL HAVE WATERPROOFING AND INSULATION IN ACCORDANCE WITH DETAILS SHOWN ON DWGS. P.1.1 THRU P.1.3.
13. ALL WALLS AND PARTITIONS SHOWN WITH MATCHING ARE INCLUDED IN THIS CONTRACT. ALL WORK WITHIN HEAVY BORDER LINES AND SHOWN UNHATCHED IS IN A SEPARATE CONTRACT BY OTHERS, UNLESS NOTED. WORK BY OTHERS INTERFACES WORK IN THIS CONTRACT, CONTRACTORS SHALL COORDINATE ALL WORK SO THAT COMPLETED WORK IS CONTINUOUS AND UNBROKEN.
14. FIREPROOF ALL DUCTS ON ELEVATIONS BIGHT 9'8 1/2" & 24'10" (1/2 2ND & 3RD FLOORS) WITH 2 SEPARATE LAYERS OF METAL LATH AND 1" VERMICULITE PLASTER HARD TO DUCTS.

ABBREVIATIONS, SYMBOLS & KEY TO MATERIALS

A.C.	AIR CONDITIONING	LAV.	LAVATORY
A.C.	ACOUSTIC	L.P.	LOW POINT
A.D.	ACCESS DOOR		
ALUM.	ALUMINUM	MACH.	MACHINE
		MAX.	MAXIMUM
BL.	BLOCK	MEMB.	MEMBRANE
BM.	BEAM	MIN.	MINIMUM
BOT.	BOTTOM	M.L.	METAL LATH
BLDG.	BUILDING	M.L.F.	METAL LATH FURRING
BD.	BOARD	M.O.	MASONRY OPENING
B.R.	BOTTOM REGISTER	M.R.	MOP RECEPTOR
		MECH.	MECHANICAL
CEM.	CEMENT	M.S.	MARBLE SADDLE
℄	CENTER LINE	MET.	METAL
CL.	CLOSET		
CEIL.	CEILING	N.I.C.	NOT IN CONTRACT
C.E.	COMBINATION ELEVATOR	N.T.S.	NOT TO SCALE
COL.	COLUMN	NO.	NUMBER
CONC.	CONCRETE		
COND.	CONDUIT	O.C.	ON CENTER
CONST.	CONSTRUCTION	OPNG.	OPENING
CONT.	CONTINUOUS	OPP.	OPPOSITE
C.T.	CERAMIC TILE	O.D.	OUTSIDE DIAMETER OR DIMENSION
CTR.	CENTER		
CAST.	CABINET	PA.	PORT AUTHORITY
CONTR.	CONTRACTOR OR CONTRACT	PARTN.	PARTITION
		P.E.	PASSENGER ELEVATOR
DET.	DETAIL	P.H.	PAPER HOLDER
D.F.	DRINKING FOUNTAIN	PL.	PLATE
DN.	DOWN	PLAS.	PLASTER
DWG.	DRAWING	PTD.	PAINTED
DIA. or ⌀	DIAMETER	POL.	POLISHED
DR.	DOOR		
		Q.T.	QUARRY TILE
EL.	ELEVATION		
ELEC.	ELECTRICAL	R.	RISER
ELEV.	ELEVATOR	RAD.	RADIUS
ESC.	ESCALATOR	R.D.	ROOF DRAIN
EQ.	EQUAL	RM.	ROOM
EQUIP.	EQUIPMENT	REF.	REFRIGERATION
EXP.	EXPOSED	R.S.	RESILIENT SADDLE
EXPAN. JT.	EXPANSION JOINT	R.T.	RESILIENT
EXTR.	EXTRUDED OR EXTRUSION	REINF.	REINFORCED OR REINFORCEMENT
EXT.	EXTERIOR	REQ'D.	REQUIRED
F.A.I.	FRESH AIR INTAKE	S.A.	SUPPLY AIR
F.H.C.	FIRE HOSE CABINET	S.E.	SERVICE ELEVATOR
FIN.	FINISH	SEC.	SECTION
FL.	FLOOR	SIM.	SIMILAR
F.R.	FIRERPROOFING	S.N.D.	SANITARY NAPKIN DISPENSER
F.R.S.C.	FIREPROOF SELF CLOSING	S.N.V.	SANITARY NAPKIN VENDOR
F.T.	FACING TILE	S.S.	SERVICE SINK
F.E.	FREIGHT ELEVATOR	ST. STL.	STAINLESS STEEL
F.D.	FLOOR DRAIN	STL.	STEEL
FIXT.	FIXTURE	SUSP.	SUSPENDED
GYP.	GYPSUM	T.C.R.	TOWEL CABINET & RECEPTACLE
GL.	GLASS	T.E.	TOILET EXHAUST
		TEL.	TELEPHONE
HORIZ.	HORIZONTAL	T.R.	TOP REGISTER
H.	HIGH	TYP.	TYPICAL
HT.	HEIGHT	T. & B.R.	TOP & BOTTOM REGISTER
H.P.	HIGH POINT	T.	TREAD
H.M.	HOLLOW METAL	T.D.	TIE DOWN
HR.	HOUR		
H.R.	HAND RAIL	V.A.T.	VINYL ASBESTOS TILE
H.V.A.C.	HEATING, VENTILATING & AIR CONDITIONING	VEST.	VESTIBULE
		V.T.	VINYL TILE
I.D.	INSIDE DIAMETER OR DIMENSION	V.W.C.	VINYL WALL COVERING
INT.	INTERIOR	VERT.	VERTICAL
INSUL.	INSULATION		
		W.D.	WOOD
JT.	JOINT	W.P.	WATERPROOFING
JAN. CL.	JANITOR'S CLOSET	W.P.	WORKING POINT
		W.	WIDE OR WIDTH
K.E.	KITCHEN EXHAUST		

RECEIVED
DEC 28 1990
LESLIE E. R[illegible]SON ASSOCIATES
211 EAST 46TH ST., N.Y.C. 10017

CONTRACT BID DRAWING date 6-25-69

NO.	DATE	ENGR. INIT.	BY
2	2-28-72	E-62	L.J.
3	7-24-70	E-16	A.H.
2	8-28-70	E-10	D.G.
1	4-8-70	E-7	D.G.
	4-8-70	E-5	D.G.
1	11-28-69	E.V.	R.C.

REVISIONS

APPROVED
CHIEF, PLANNING DIVISION
DATE

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: NORTHEAST PLAZA BUILDING
FINISH SCHEDULE

DRAWN | CHECKED
SCALE | DATE 7-28-69
PROJECT NUMBER | SHEET OF
DRAWING NUMBER A-E