NORTH

Notes:
1. FOR GENERAL NOTES KEY TO MATERIALS, ABBREVIATION & FINISH SCHEDULE, DOOR SCHEDULE & SCHEDULE OF DRAWINGS SEE DRAWINGS A-E.1 TO A-E.4
2. FOR COMPLETE 1/8" SCALE CORE PLAN SEE DRAWING A-E.20
3. ALL ELEVATIONS INDICATED THUS (16'0") ARE SHOWN IN RELATION TO FINISH FLOOR.
4. FOR ALL MECHANICAL & ELECTRICAL LAYOUTS SEE RESPECTIVE SHOP HEADS DRAWINGS
5. FOR TYPICAL STAIR DETAILS SEE DRAWING A-E.106
6. ALL TRENCH HEADERS TO BE FIREPROOFED ATMOSPHERIDE OF SLAB FOR A WIDTH OF 6'0" WITH A SPRAY-ON FIREPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEERS & CONTRACTORS APPROVED SHOP DRAWING FOR LOCATION & EXTENT OF TRENCH HEADERS AND FIREPROOFING.
7. FINISHED FLOOR ELEVATION AND TOP OF SLAB ELEVATION ARE (-2'-0") UNLESS OTHERWISE SHOWN OR NOTED
8. CUNTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 2" ACTUAL PROJECTION IN RENTABLE SPACE AND SHALL BE MINIMUM 76" FROM HORIZONTAL. SEE TYPICAL DETAIL
9. CORRIDOR AND TOILET LIGHTING LAYOUTS ARE AS SHOWN FOR ALL OTHER LIGHTING SEE ELECTRICAL DRAWINGS AND ARCHITECTURAL DETAILS
10. FOR PARTS AND SUB-DIVISION OF TENANT SPACE SEE TENANT ARCHITECTS DRAWINGS
11. FOR FIREPROOFING OF ALL FREE STANDING COLUMNS WITHIN PERIMETER WALL NOT SHOWN OR NOTED ON THIS PLAN OR CORE PLAN PROVIDE SPRAY-ON TYPE FIREPROOFING AROUND COLUMNS AND FINISH WITH METAL STUDS AND ⅝" GYPSUM WALLBOARD SEE TYPICAL DETAILS ON DWG. A-E.104
12. ALL PARTITIONS SHOWN UNHATCHED ARE NOT INCLUDED IN THIS CONTRACT
13. EXTERIOR WALL DIMENSIONS ARE TO BE USED ONLY FOR LOCATION OF POINT CENTERLINE AND FOR NUMBER OF WINDOW SPACES. FOR SIZE OF MULLIONS AND OVERALL DIMENSIONS SEE APPROVED SHOP DRAWINGS

TENANT SPACE

TENANT SPACE

TENANT SPACE

TENANT SPACE (SEMI CLOSED)

TENANT SPACE

PIPE SHAFT SEE DETAIL THIS SHEET

PIPE SHAFT SEE DETAIL THIS SHEET

DETAIL OF PIPE SHAFT AT COLUMN P1
SCALE ½"=1'-0"

DETAIL OF PIPE SHAFT AT COLUMN P2
SCALE ½"=1'-0"

RECEIVED
DEC 28 1970
LESLIE E. ROBERTSON ASSOCIATES
211 EAST 43RD ST., N.Y.C. 10017

KEY PLAN

MATCH LINE 'B'
FOR CONTINUATION OF PLAN SEE DRAWING A.E.-37

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT B/D DRAWING date 6-22-67

NO.	DATE	SUB. NO.	BY
A	7-18-72	E-68	L.C.
A	2-28-72	E-48	L.C.
A	10-7-71	E-45	L.C.
A		E-37	L.C.
A	3-6-71	E-25	L.C.
A	4-16-70	E-3	D.G.
A	4-16-70	E-5	D.G.
A	4-15-70	E-7	D.G.
A	11-26-69	E-1	L.C.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION
DATE

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING UTILITIES, FOUNDATIONS

TITLE: NORTHEAST PLAZA BUILDING
5TH FLOOR PLAN-WEST
OFFICE FLOOR

DRAWN		CHECKED	
SCALE	1/8"=1'-0"	DATE	7-28-69
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-E-37		