NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-A-1 TO A-A-5.
2. FOR COMPLETE 1/8" SCALE FLOOR PLAN, SEE DRAWING A-A-101
3. ALL ELEVATIONS GIVEN THUS (234.5) ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEER'S DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG. # A-A-6-204 AND A-A-6-206.
6. ALL TRENCH HEADERS TO BE PREPREPARED AT UNDERSIDE OF SLAB FOR A WIDTH OF 4'-0" WITH A SPRAY-ON TYPE OF PREPROOFING SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE & ELECTRICAL ENGINEER'S CONTRACTORS APPROVED SHOP DWGS. FOR LOCATION & EXTENT OF TRENCH HEADERS & PREPROOFING.
7. FINISH FLOOR ELEVATIONS AND TOP OF SLAB ELEVATIONS ARE (234.5) UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMENS TOILETS ONE DISPENSER AT EACH LAVATORY ACCESS DOORS TO SOAP DISPENSER SHALL TO BE LOCATED IN ACCORDANCE WITH TILE CONTRACT. SEE TYPICAL TOILET DETAILS DWG # A-AB-206
9. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS, STAIRS, DUCTS, ETC., BOTTOM ELEVATION OF ALL FINISHED AND BUCTWORK SHALL BE MAINTAINED AT 8'-2" ABOVE FINISHED FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: _____
11. CENTER REQUIRED ON ALL DRAIN PROJECTIONS OVER 6¾" NOMINAL ("E" ACTUAL) DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 7'0" FROM HORIZONTAL. SEE TYPICAL DETAILS
12. FOR PREPROOFING OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-AB-206 TO A-AB-208.

COLUMN DETAIL

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT NO.	DRAWING	DATE 3-7-68
	1-30-70	A-B4 B.C.
	1-30-70	A-B5 L.L.
	1-30-70	A-17 L.L.
	5-25-66	A-14 D.I.
	5-25-66	A-16 D.I.
6-18-71 1-164	5-25-66	A-17 D.I.
4-1-71 4-188	5-25-66	A-15 D.I.
5-12-76 A-78	8-1-66	A-10 P.G.
5-12-76 A-78	6-10-66	A-5 P.G.
1-30-70 A-81	6-1-66	A-3 P.G.

REVISIONS — DATE | BULL. NO. | BY

REVISIONS — DATE | BULL. NO. | BY

REGISTERED ARCHITECT — STATE OF NEW YORK — NO. 17

APPROVED: CHIEF, PLANNING DIVISION — DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY — PLUMBING, UTILITIES, FOUNDATIONS

TITLE: 66TH FLOOR CORE PLAN

SCALE: 1/8"=1'-0" — DATE: 3-7-68

DRAWING NO. A-A-105