NORTH

## NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, PLUMBING SCHEDULES, DWGS., SYMBOLS AND TERMINOLOGY, SEE DRAWING P-1.01, TO A.A.-5.
2. FOR COMPLETE 1/8" SCALE FLOOR PLAN SEE DRAWING A.A.-100.
3. ALL DIMENSIONS SHOWN ARE (UNLESS OTHERWISE NOTED) TO FINISH FACES.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS, SEE RESPECTIVE ENGINEERS' DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG. A.A.-0.144 AND A.A.-0.145.
6. ALL TRENCH HEADERS TO BE PROVIDED AT UNDERSIDE OF SLAB FOR A WIDTH OF 6'-0" WITH A DEPTH AS SHOWN TYP. EXCEPTIONS, SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEERS AND CONTRACTORS APPROVED SHOP DWGS. FOR LOCATION & EXTENT OF TRENCH HEADERS AND RACEWAYS.
7. FINISH FLOOR ELEVATIONS AND TOP OF SLAB ELEVATIONS ARE (2.0125') BELOW FINISHED FLOOR, U.N.O.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS. COIN DISPENSERS AT EACH JANITOR'S ACCESS CLOSET TO SOAP DISPENSER SHALL BE LOCATED IN ACCORDANCE WITH THE CONSTRUCTION AND TYPICAL TOILET DETAILS DWG'S. A.A.-316.
9. WHERE NO RUN CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS, STAIR RECESSES, ETC., BOTTOM ELEVATION OF ALL BEAMS AND ELECTRICAL BOXES SHALL BE MAINTAINED AT 10'-0". FINISHED FLOORS, TO PROVIDE FOR PROPER CEILING INSULATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR, CEILING AS INDICATED THUS: _____
11. CENTER LINES USED ON ALL REFLECTED PLANS SHOWN THUS: _____ ARE ORIGINAL DESIGN DIMENSIONS IN ELEVATOR SHAFTS AND SHALL BE MAINTAINED AT FINISH CONSTRUCTION. SEE TYPICAL DETAILS
12. FOR DIMENSIONS OF FIXED EQUIPMENT, COLUMNS AND TYPICAL PARTITION DETAILS SEE DWGS. A.A.-0.100 TO A.A.-0.107.

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

| CONTRACT | BID | DRAWING | Date | S-I-S-B |
|---|---|---|---|---|
| | | 1-30-70 | A-64 | A.C. |
| | | 1-30-70 | A-81 | A.C. |
| | | 1-30-70 | A-88 | A.C. |
| | | 1-30-70 | A-97 | L.J. |
| 6-1-78 | A-1067 | 6-16-69 | A-31 | D.G. |
| 1-15-70 | A-1018 | 6-16-69 | A-70 | D.G. |
| 5-12-71 | A-1064 | 6-16-69 | A-17 | D.G. |
| 6-1-71 | A-1103 | 8-1-68 | A-10 | D.G. |
| 7-12-72 | A-74 | 9-13-68 | A-3 | D.G. |
| 5-12-73 | A-73 | 4-29-68 | A-5 | D.G. |

REVISIONS — DATE | DWG. NO. | BY

REVISIONS — DATE | DWG. NO. | BY

APPROVED: CHIEF, PLANNING DIVISION — DATE

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT
EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT
WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS
JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS
JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS
THE PORT OF NEW YORK AUTHORITY — PAVING, UTILITIES, FOUNDATIONS

TITLE: 6TH FLOOR CORE PLAN
SCALE: 1/8"-0" — DATE: 7-20-67
DRAWING NO. A-A-107