NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS ROOM SCHEDULES, DOOR SCHEDULES AND SCHEDULES, OR DRAWINGS SEE DRAWINGS A-1.1 TO A-1.4
2. FOR COMPLETE "B" SCALE FLOOR PLAN SEE DRAWING A-A-110
3. ALL ELEVATIONS GIVEN THUS (A0'0") ARE IN ADDITION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. ALL TYPES THUS "DRYWALL" SEE SYMBOLS-ROOM SCHEDULES AND SHEETS
6. ALL 7'6 INCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 4'-0" MIT. A GAP-IN TYPE OF FIREPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE & ELECTRICAL ENGINEERS & CONTRACTORS APPROVED SHOP DRAWINGS FOR LOCATION & EXTENT OF TRENCH HEADERS & FIREPROOFING.
7. FINISH FLOOR ELEVATIONS ARE TOP OF SLAB ELEVATIONS ARE (SOG) UNLESS OTHERWISE SHOWN OR NOTED.
8. PLUMBING RISER DRAWINGS AT ALL MEN AND WOMENS "T" TYPE DRY STANDPIPES AT EACH LEVEL EXIT ACCESS DOORS TO BE LOCATED IN ACCORDANCE WITH TILE COLORS. SEE TYPICAL TOILET SCALE SIZE 1/4"-1'-0"
9. WHILE NO SUSPENDED CEILINGS ARE CALLED FOR, EVEN AS IN CLOSETS, STAIR, HOISTWAYS ETC., BOTTOM ELEVATION OF ALL PIPING AND ELECTRICAL SHALL BE MAINTAINED AT 8'-4" ABOVE FINISHED FLOOR, TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: ————————
11. CANTS ARE REQUIRED SHALL BEAM FURRED TYPE OVER 6" NOMINAL (ACTUAL) DIMENSION OF ELEVATOR SHAFTS AND SHALL BE MINIMUM 10" FROM MATERIAL. SEE TYPICAL DETAILS
12. FOR REMOVING OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-1.1-106 TO A-1.1-112.

SECTION A/A

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT NO. DRAWING date 5-9-66

NO.	DATE	BULL. NO.	BY
6	6-15-71	A-184	DBL
5	5-15-70	A-75	AH
4	1-30-70	A-31	AS

REVISIONS

NO.	DATE	BULL. NO.	BY
A	1-30-70	A-69	LM
A	1-30-70	A-97	LM
A	5-29-69	A-94	DAL
A	5-29-69	A-86	DAL
A	5-29-69	A-77	DAL
A	5-29-69	A-89	DAL
A	11-1-68	A-74	AM
A	8-1-68	A-40	DAL
A	7-29-68	A-8	DAL
A	5-15-68		DAL

REVISIONS

APPROVED
CHIEF, PLANNING DIVISION
DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES & DRAINAGE

1/8"-1'-0"

69th Floor - Core Plan

SCALE 1/8"=1'-0" DATE 7-31-67
DRAWN CHECKED
APPROVED SHEET

A-A-111