NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES & SCHEDULE OF DRAWINGS SEE SHEET "A" SERIES.
2. FOR COMPLETE G.F.S. AXIS PLANS, PLAN AND SHTS. OF AXIS SEE A-1.
3. ALL ELEVATIONS SHOWN THUS (XX'-XX") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL & ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DWGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG'S A-A3-201 AND A-A3-202
6. ALL TRENCH HEADERS TO BE RELAID OVER AT UNDERSIDE OF SLAB FOR A WIDTH OF 4'-0" WITH A SUPPLY OF TYPE OF FOLLOWING SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE & ELECTRICAL ENGINEERS & CONTRACTORS APPROVED SHOP DWGS. FOR LOCATION & EXTENT OF TRENCH HEADERS & FILLER PLATES.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE EQUAL UNLESS OTHERWISE SHOWN OR NOTED.
8. BRONZE EYES DIFFERENTIALS AT ALL MEN AND WOMEN'S TOILETS
9. PIPE SPACERS AT ELECTRICAL ACCESS DOORS TO KEEP DISTRIBUTION VALVES TO BE LOCATED IN ACCORDANCE WITH I. COLCEVIC SEE TYPICAL DWG. A-A3-201
10. WHERE NO FURRED CEILINGS ARE SHOWN FOR, EVEN IF IN CLOSETS, STAIR, ELEVATORS ETC. BOTTOM ELEVATION OF ALL BEAMS AND DUCTWORK SHALL BE MAINTAINED AT 8'-4" ABOVE FINISHED FLOOR TO ALLOW FOR SUITABLE CEILING INSTALLATION AND CLEARANCE OF FULL 12'-0" DOORS
11. EXTENT OF PUBLIC CEILING IS INDICATED THUS
12. CAULTS REQUIRED ON ALL BEAM PENETRATIONS OVER 6" HORIZONTAL (GENERAL) DIMENSION IN ELEVATION, CAULTS SHALL BE MINIMUM 24" FROM HORIZONTAL SEE TYPICAL DETAILS
13. FOR SHEETROCKING OR BRICK STACKING SEE ARCHITECTURAL SPECIFICATIONS
14. DETAILS SEE DRAWINGS A-A3-203 TO A-A3-207.

NORTH

PART PLAN AT 71ST FLOOR

PART PLAN AT 71ST FLOOR

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT	NO.	DRAWING	DATE	BY
		1 1-30-70	A-51	LJL
		2 1-30-70	A-48	LJL
		3 1-30-70	A-47	LJL
		4 5-15-69	A-51	DG
		5 5-15-69	A-50	DG
		6 5-15-69	A-17	DG
		7 5-15-69	A-95	DG
		8 3-1-68	A-10	DG
6-18-71	A-106	CB1 9 1-28-68	A-6	DG
5-15-70	A-75	LJL 10 4-29-66	A-5	DG

NO. DATE REVISIONS BY — NO. DATE REVISIONS BY

REGISTERED ARCHITECT STATE OF NEW YORK

APPROVED
CHIEF, PLANNING DIVISION
DATE

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
EMERY ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, RESTUTTING, FOUNDATIONS

TITLE: 70TH & 71ST FL. CORE PLAN

DESIGNED		CHECKED	
SCALE	1/8" = 1'-0"	DATE	1-30-70
TRACED		SHEET	OF
APPROVED			

DRAWING NO. A-113