NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FIRE RESISTANCE RATINGS, ETC. SEE DRAWING "A-0.1 TO A-0.4".
2. FOR COMPLETE 81ST FLOOR PLAN, SEE DWG. "A-81.1".
3. ALL ELEVATIONS SHOWN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL & ELECTRICAL LAYOUTS SEE RESPECTIVE SUBCONTRACT DWGS.
5. FOR TYPICAL STEEL DETAILS SEE DWGS. "A-0.5-1 TO A-0.5-7".
6. ALL TRENCH HEADERS TO BE FURNISHED BY CONTRACTOR OF SLAB (SEE "A-0.1 TYP. SLAB DETAILS") WITH A MINIMUM TYPE 1 CONCRETE COVER. FOR ARCHITECTURAL SYMBOLS, ABBREVIATIONS, ETC., TYPE AND MATERIAL FURNISHED & INSTALLED BY CONTRACTOR EMPLOYED SEE DWGS. FOR LOCATION & EXTENT OF TRENCH HEADERS AND PARTITIONS.
7. FINISH FLOOR ELEVATION +0.1" TOP OF SLAB ELEVATIONS ARE GIVEN UNLESS OTHERWISE SHOWN OR NOTED.
8. REFER ENLARGED PLANS FOR ALL MECHANICAL TOILET ROOMS, DRINKING FOUNTAINS, SERVICE SINKS, ETC. ALL TOILET ROOMS TO BE EQUIPPED WITH ONE DISPENSER FOR ENTIRE FLOOR, ACCESSIBLE TO BOTH SEXES AS SHOWN ON ENLARGED PLANS.
9. FOR LOCATION OF TOILET ROOMS SEE DWGS. "A-81.1 & A-81.2".
10. PARTITIONS ABOVE CEILINGS SHALL BE CONSTRUCTED WITH TYPE "X" GYPSUM WALLBOARD AS REQUIRED BY LOCAL CODES. WHERE PARTITIONS ARE CALLED FOR AS NON-COMBUSTIBLE, STEEL PARTITIONS SHALL BE USED.
11. WHERE ENCLOSURES OF ALL PIPING AND DUCTWORK SHALL BE PROVIDED AT 8'-0" ABOVE FINISHED FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEAN-OUTS AT ALL CONVENIENT POINTS.
12. ALL CORRIDOR WIDTHS ARE 6'-0" UNLESS NOTED OTHERWISE.
13. ALL CEILING HEIGHTS ARE 8'-0" UNLESS NOTED OTHERWISE.
14. ALL DOORS ARE 3'-0" WIDE UNLESS NOTED OTHERWISE.
15. ALL DOORS ADJACENT TO ELEVATORS SHALL BE SELF-CLOSING TYPE.
16. ALL DOORS TO BE FLUSH WOOD TYPE UNLESS NOTED OTHERWISE.
17. ALL DOORS TO BE 7'-0" HIGH UNLESS NOTED OTHERWISE.
18. ALL DOORS TO BE HUNG WITH BALL BEARING BUTTS UNLESS NOTED OTHERWISE.
19. ALL DOORS TO BE HUNG WITH BALL BEARING BUTTS UNLESS NOTED OTHERWISE.
20. ALL DOORS TO BE HUNG WITH BALL BEARING BUTTS UNLESS NOTED OTHERWISE.

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT	NO.	DRAWING	date 2-9-68
	1	1-30-70	A-53
	2	1-30-70	A-67
	3	6-23-69	A-81
	4	6-23-69	A-56
	5	6-23-69	A-11
A-10-71	6	8-25-69	A-15
A-10-72	7	11-1-68	A-11
A-103	8	8-1-68	A-10
A-105	9	8-28-68	A-8
A-9	10	8-28-68	ALL

REVISIONS

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT
EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT
WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS
JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS
JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS
THE PORT OF NEW YORK AUTHORITY — PAVING, UTILITIES, FOUNDATIONS & SITE WORK

TITLE: 81ST FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	1/8"=1'-0"	DATE	7-8-68
PROJECT NUMBER		SHEET	65
DRAWING NUMBER	A-A-137		