NORTH

NOTES

A. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES AND SCHEDULES OF DOORS SEE DRAWINGS A-A-01 TO A-A-04.

B. FOR COMPLETE 8" SCALE PLANS SEE DWG # A-A-100.

C. ALL ELEVATIONS GIVEN THUS (0'-0") ARE IN RELATION TO FINISH FLOOR.

D. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS

E. FOR TYPICAL STAIR DETAILS SEE DWG # A-A-104 & A-A-105 & A-A-106

F. ALL TRENCH HEADERS TO BE FIREPROOFED AT THICKNESS OF SLAB FOR 1 HOUR @ 4'-0" WITH A SPRAY-ON TYPE FIREPROOFING SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND SUBC ENGINEERS & CONTRACTORS SHOP DWGS FOR EXACT LOCATION & EXTENT OF TRENCH HEADER AND FIREPROOFING.

G. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (-0'-0") UNLESS OTHERWISE SHOWN OR NOTED.

H. PROVIDE SUMP DEPRESSIONS AT ALL TOILETS AND NURSES TOILETS, ONE DEPRESSION 4" DEEP LOCATED ACCESS DOOR TO BE DEPRESSED TO BE LOCATED IN ACCORDANCE WITH THE FOLLOWING. SEE TYPICAL TOILET DETAILS SHEET A-A15-104.

I. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS, STAIR PASSAGES ETC. BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE MAINTAINED AT 8'-0" ABOVE FINISHED FLOOR TO ENSURE PROPER INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.

J. EXTENT OF PUBLIC CORRIDOR, AS INDICATED THUS: [illegible]

K. CURTS ARE ASSUMED ON ALL BEAM PENETRATIONS WHEN 6" MINIMUM (8" ACTUAL) DIMENSION IN ELEVATION. BULLETS SHALL BE 4" MINIMUM (5" ACTUAL) SEE TYPICAL DETAILS

L. FOR DIMENSIONS OF PIPES STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-A8-106 TO A-A8-116

M. EXTENT OF PUBLIC CORRIDOR, AS INDICATED THUS: [illegible]

N. CURTS ARE ASSUMED ON ALL BEAM PENETRATIONS WHEN 6" MINIMUM (8" ACTUAL) DIMENSION IN ELEVATION. BULLETS SHALL BE 4" MINIMUM (5" ACTUAL) SEE TYPICAL DETAILS

O. FOR DIMENSIONS OF PIPES STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-A8-106 TO A-A8-116

SECTION A/139

SECTION B/139

C/139 D/139 SCALE 1/8"=1'-0"

E/139 F/139 SCALE 1/8"=1'-0"

BULLETINS NOT DRAWN HERE IN THE PROCESS OF COMPLETION

CONTRACT	BID	DRAWING	date 8-7-68	
		5	5-15-70	A-13
		4	1-30-70	A-51
		3	1-30-70	A-51
		2	1-13-70	A-47
6-18-71	A-118	1	5.28.69	A-51
6-18-71	A-104	0-1	5.28.69	A-26
6-18-71	A-105	0-7	5.28.69	A-17
9-1-71	A-123		5.28.69	A-28
11-8-70	A-118	1-1	8-1-68	A-40
11-8-70	A-120	1-2	8-28-68	A-8

NO.	DATE	DWG. NO.	BY
REVISIONS			

NO.	DATE	DWG. NO.	BY
REVISIONS			

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES MINORU YAMASAKI, ARCHITECT	EMERY ROTH & SONS RICHARD ROTH, ARCHITECT
WORTHINGTON, SKILLING, HELLE & JACKSON STRUCTURAL ENGINEERS	JAROS, BAUM & BOLLES MECHANICAL ENGINEERS
JOSEPH R. LORING & ASSOCIATES ELECTRICAL ENGINEERS	THE PORT OF NEW YORK AUTHORITY PAVING, UTILITIES, FOUNDATIONS

1/8"=1'-0"

TITLE: 82ND FLOOR CORE PLAN

DRAWN		CHECKED	
NO.	1/8"=1'-0"	DATE	7-31-67
PROJECT NUMBER		SHEET	OF
CONTRACT NUMBER			A-A-139