NORTH

NOTE
FIREPROOF DUCTS ABOVE WITH 4 REMOVABLE LOUVERS OF METAL LATH 11" FURRING TO PLASTER. RUNS TO DUCTS ABOVE SEAL FOR FIRE-STOP OR PREFABRICATING.

CORRIDOR

ELEVATOR MACHINE RM.

ELEV. LOBBY

AC SHAFT

SERVICE ROOM

SAFRA SHAFT

TENANT SPACE

ELEVATOR MACHINE ROOM

SECONDARY WATER PUMP

ELEVATOR PENTHOUSE

SECTION

COL. 701 & 801

COL. 803

COL. DETAILS

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-0.1 TO A-0.5.
2. FOR COMPLETE "B" SCALE FLOOR PLAN SEE DRAWING A-B-101
3. ALL ELEVATIONS GIVEN THUS CB(C) ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS
5. FOR TYPICAL STAIR DETAILS SEE DWGS. A-B-004 AND A-B-005.
6. ALL TRENCH HEADERS TO BE FIREPROOFED AT WORKFACE OF SLAB FOR A WIDTH OF 6'-0" WITH 2 COAT-ON TYPE FIREPROOFING, SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEER AND CONTRACTOR'S APPROVED SHOP DRAWING FOR LOCATION AND EXTENT OF TRENCH HEADER AND INSERTIONS.
7. FIN. FL. ELEV. ELEVATION AND "TOP OF SLAB ELEVATIONS ARE "B" UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE DISPENSERS AT ALL MEN AND WOMENS TOILETS. FOR LOCATION ACCESS DOORS TO SHAFTS SEE DRAWINGS A-B-101 TO A-B-104 INCLUSIVE.
9. ALL CEILINGS ARE CALLED FOR SHOWN AT 8'-0" A.F.F. UNLESS OTHERWISE NOTED. BOTTOM ELEVATION OF ALL FURRING AND SUSPENDED CEILINGS SHALL BE MAINTAINED AT 8'-0" ABOVE FINISHED FLOOR TO PROVIDE MINIMUM CEILING INSTALLATION AND CLEARANCE 7'-8" CLR. AT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: - - - - - -
11. CHASES ARE PLANNED ON ALL BEAM PROJECTIONS OVER 6" NOMINAL (6" ACTUAL) DIMENSION IN ELEVATOR SHAFTS AND SMALL BE MAXIMUM OF 24 INCH HORIZONTAL SEE TYPICAL DETAILS.
12. FOR PREFABRICATING OF FLAT SPANDRAL COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-B-301 TO A-B-315.

BULLETINS NOT DATED ARE IN THEIR APPROPRIATE OR CHRONOLOGICAL ORDER OF COMPLETION

CONTRACT	BID	DRAWING	Date 5-1-68		
			1-30-70	A-61	E.C.
			1-30-70	A-65	E.C.
			1-30-70	A-67	E.C.
			8-28-61	A-96	D.D.
			8-28-69	A-97	D.D.
			8-28-69	A-98	D.D.
			11-1-68	A-11	E.C.
			6-4-68	A-10	E.C.
			6-19-68	A-8	E.C.
			" " 68		J.V.L.

NO.	DATE	SUB. NO.	BY
1	6-18-71	A-134	L.J.
2	7-1-71	A-135	

REVISIONS

NO.	DATE	SUB. NO.	BY

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — EMERY ROTH & SONS
MINORU YAMASAKI, ARCHITECT — EMERY ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON — JAROS, BAUM & BOLLES
STRUCTURAL ENGINEERS — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — THE PORT OF NEW YORK AUTHORITY
ELECTRICAL ENGINEERS — PAVING, UTILITIES, FOUNDATIONS

TITLE: 95TH FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	1/8"	DATE	7-1-67
PROJECT ENGINEER		CHECK	
DRAWING NUMBER	A-A-151		