NORTH

TENANT SPACE
CHANNEL "A"

CORRIDOR

SAIBA SHAFT

CLEAR LOBBY

STAIR SHAFT

ELEV. SHAFT

A.C. FLUR.

STAIR ROOM

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR, INTERIORS AND INTERIORS OF DRAWINGS SEE DRAWINGS # A-A1 TO A-A6.
2. FOR COMPLETE 16" SCALE FLOOR PLAN SEE DRAWING # A-A15.
3. ALL ELEVATIONS GIVEN THUS (100'0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS, SEE PROPERTIES ENGINEERS DRAWING
5. FOR TYPICAL STAIR, DETAILS SEE SHEETS A-B-104 AND A-A-B-104
6. ALL FINISH MARBLE TO BE PROVIDED AT ENCLOSURE OF ELEV. PIT, 3 WIDTH OF 6'0" WITH 1 STRAIGHT TYPE WATERPROOFING, SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEERS AND CONTRACTORS APPLYING FOR PLUMBING FOR LOCATION AND EXTENT OF TRENCH HEADER, AND PREPARATIONS.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (16'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS AND DISPENSERS AT EACH LAVATORY, SEATS, SEATS TO BE SURFACE MOUNTED TO BE INSTALLED WITH FULL SECTION TO THE TYPICAL TOILET AS PER SHT. # A-A-B-104.
9. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR THEY ARE TO BE CLOSETS, STAIR TOWERS ETC. BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK TO BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION, AND CLEARANCE OF ALL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: _____
11. CANTS ARE REQUIRED ON ALL BEAMS PROJECTING OVER 4'0" NOMINAL (STARTING) DIMENSION IN ELEVATION, CANTS SHALL BE MINIMUM 2'0" FROM WORKING LINE. SEE TYPICAL DETAILS
12. FOR FIREPROOFING OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-A5-B16 TO A-A5-B12.

CONTRACT NO. DRAWING: Arch S-2-68

NO.	DATE	BULL. NO.	BY
1	9-28-74	A-406	LJ
2	9-25-74	A-416	LJ
3	6-1-78	A-553	LJ
4	VOID	A-565	LJ
5	8-28-78	A-585	LC
6	11-27-78	A-597	LC
7	4-18-79	A-603	DT
8	10-16-79	A-664	DT
9	4-1-79	A-625	LJ
10	6-1-79	A-625	LJ
11	9-8-79	A-680	LJ

REVISIONS

NO.	DATE	BULL. NO.	BY
12	11-6-80	A-708	LJ
13	4-29-80	A-81	J.
14	1-30-79	A-51	AB
15	1-30-79	A-53	AB
16	1-30-79	A-47	LJ
17	5-25-64	A-51	LJ
18	3-23-64	A-16	LJ
19	8-21-64	A-17	LJ
20	5-26-64	A-23	LJ
21	6-11-68	A-40	DB

REVISIONS

REGISTERED ARCHITECT

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES MINORU YAMASAKI, ARCHITECT	EMERY ROTH & SONS RICHARD ROTH, ARCHITECT
WORTHINGTON, SKILLING, HELLE & JACKSON STRUCTURAL ENGINEERS	JAROS, BAUM & BOLLES MECHANICAL ENGINEERS
JOSEPH R. LORING & ASSOCIATES ELECTRICAL ENGINEERS	THE PORT OF NEW YORK AUTHORITY PAVING, UTILITIES, FOUNDATIONS

TITLE: 104TH FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	1/16"	DATE	7-8-69
TRACED			
CHECKED			

A-A-160

1/16"-1'0"