NORTH

NOTE:
PARAPET DUCTS ABOVE 8th'S SYMBOLIZE LAYERS OF METAL LATH & 1" MINIMUM PLASTER ADD TO DUCT SIZES SHOWN ON DRAWINGS FOR EXTENT OF FIREPROOFING

CORRIDOR

NOTE:
CEILING IN BLAB ABOVE FOR REFUSE STATION

NOTE:
CEILING IN BLAB ABOVE FOR REFUSE STATION

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-A-1 TO A-A-9.
2. FOR COMPLETE 16" SCALE FLOOR PLAN SEE DRAWING A-A-101.
3. ALL ELEVATIONS GIVEN THUS (EL00'0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DRAWINGS A-A-B-106 AND A-A-B-108.
6. ALL TRENCH HEADERS TO BE WATERPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 2'-0" WITH A BITUMEN TYPE WATERPROOFING AS ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEERS AND CONTRACTORS MUST CONFER AND COORDINATE FOR LOCATION AND EXTENT OF TRENCH HEADER AND POURMARKS.
7. FINISH FLOOR ELEVATION (TOP OF SLAB ELEVATIONS) ARE (105'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SHOP DRAWINGS AT ALL NEW AND REMOVAL POINTS.
9. THE DOOR NOTES (1) EACH LAUNDRY ACCESS DOORS TO SHOW DISPENSERS, VALVES TO BE LOCATED IN ACCORDANCE WITH THE CONSING SEE TYPICAL TOILET DETAILS A-A-B-106 & 108.
10. WHERE FURRING OCCURS AT EXTERIOR WALLS, IT SHALL BE CALLED FOR WITH OUT NO EXCEPTS. ETHER PRESSURE ETC. - BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE APPROVED AT SHOP DRAWING STAGE TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
11. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: _____
12. CENTS ARE DERIVED ON ALL BASIS PARTITIONS EVEN 4½" NOMINAL (ACTUAL) DIMENSIONAL ALLOWANCE GIVEN FOR AND SHALL BE MINIMUM 7½" FROM CORE TO TAIL. SEE TYPICAL DETAILS.
13. FOR PREFIXING OF FREE STANDING CEILINGS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-A-B-106 TO A-A-B-108.

						CONTRACT BID DRAWING date 6-9-65				
						6-16-7	A-170	DG	5-13-70	A-73
						6-16-7	A-166	DT	1-30-70	A-81
9-29-74	A-606	L.J.				6-16-7	A-165	L.J.	1-30-70	A-83
9-29-74	A-446	L.J.				9-1-71	A-170		1-30-70	A-87
9-29-74	A-444	L.J.				9-1-71	A-169		5-13-91	A-91
11-15-74	A-995	L.J.				9-1-71	A-163		5-13-91	A-93
5-1-76	A-966	L.J.				9-1-70	A-97		5-13-91	A-96
VOID	A-958	L.J.				6-22-70	A-96		5-13-91	A-97
1-19-76	A-913	L.C.				6-22-70	A-97		5-13-91	A-10
10-17-7	A-907	L.C.				6-22-70	A-96		5-13-91	A-
NO. DATE : BULLO BY						NO. DATE : BOR. NO. BY			NO. DATE : BOR. NO.	
REVISIONS						REVISIONS			REVISIONS	

BULLETINS NOT LISTED ARE IN THE PROCESS OF COMPLETION

REGISTERED ARCHITECT

ASSOCIATES
CAMP, FLOMENHOFT, STONE

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES MINORU YAMASAKI, ARCHITECT	EMERY ROTH & SONS RICHARD ROTH, ARCHITECT
WORTHINGTON, SKILLING HELLE & JACKSON STRUCTURAL ENGINEERS	JAROS, BAUM & BOLLES MECHANICAL ENGINEERS
JOSEPH P. LORING & ASSOCIATES ELECTRICAL ENGINEERS	THE PORT OF NEW YORK AUTHORITY PAVING, UTILITIES, LANDSCAPING

TITLE: 105TH FLOOR CORE PLAN

DATE		CHECKED	
SCALE	1/16" = 1'-0"	DATE	1967
PROJECT NUMBER		TYPED	
DRAWING NUMBER	A-A-162		