NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULE & DOOR SCHEDULE & SCHEDULE OF DRAWINGS SEE DRAWINGS A-1.1 TO A-1.4.
2. FOR COMPLETE FLOOR PLANS SEE DRAWINGS A-2.1A TO A-2.7D.
3. ALL ELEVATIONS GIVEN THUS (70'-0") ARE IN RELATION TO HIGH FLOOR.
4. FOR MECHANICAL & ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS' DRAWINGS.
5. FINISH FLOOR ELEVATION & TOP OF SLAB ELEVATIONS ARE (70'-0") UNLESS OTHERWISE SHOWN OR NOTED.
6. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS, STAIR LANDINGS ETC., BOTTOM ELEVATION OF ALL FURRING & PARTITIONS SHALL BE MAINTAINED AT 8'-6" ABOVE FINISH FLOOR, TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
7. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 2½" NOMINAL (3" ACTUAL) DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MIN. HOUR 15° FROM HORIZONTAL. SEE TYPICAL DETAILS.
8. FOR TYPICAL PARTITION DETAILS SEE DRAWING "A" AND PARTITION SCHEDULE ON DRAWING A-1.3.
9. FOR MECHANICAL EQUIPMENT ROOM HEIGHTS SEE DRAWINGS P-A.1 (R) TO A-4.1 (R).
10. ALL WALLS, PARTITIONS (ALSO SHOWN WITH HATCHING) ARE IN THIS CONTRACT, UNLESS NOT DETAILED (R.U.) & SEPARATE CONTRACT BY OTHERS. WHERE WORK BY OTHERS INTERFACES WORK IN THIS CONTRACT, CONTRACTOR SHALL COORDINATE ALL WORK SO THAT COMPLETED WORK IS CONTINUOUS AND UNIFORM. ALL DIMENSIONS SHOWN ON WORK BY OTHERS IS FOR COORDINATION ONLY.

ROOF
1" BUILT-UP ROOFING WITH GRAVEL IN PLACE ON
2" RIGID INSULATION OVER MEMBRANE
3" PRE-CAST CONCRETE ROOF SLAB OVER INSULATION

ROOF STAIR
R.F.B. (+2'-6")
TOP OF SLAB EL. (+0'-6")
TOP OF SLAB EL. (+7'-6")
HANDRAIL AT TOP OF SLAB WITH CONC. PAN STAIRS.

ELEVATOR MACHINE ROOM

UPPER PART OF MECHANICAL EQUIPMENT ROOM

MECHANICAL EQUIPMENT ROOM

TENANT SPACE

SECONDARY MOTOR ROOM
TOP OF SLAB EL. (+0'-6")

CORRIDOR

ELEC. CL. 'C'

ELEVATOR SHAFT

ELEVATOR LOBBY

FIRE RESERVE & EXPANSION TANK ROOM

WINDOW WASHER STORAGE

F.F. #99

F.F. #80

CONTRACT	BID	DRAWING	date		
			9-25-72	A-507	DG
			10 I D	A-906	L.J.
			6-1-73	A-556	L.J.
			12-27-73	A-199	L.C.
			11-27-74	A-196	L.C.
			9-19-11	A-176	GBL
9-25-74	A-459	J.R.	6-18-75	A-166	D.T.
	A-607	J.R.	6-18-75	A-166	L.J.
1-29-76	A-568	L.J.	2-1-77	A-123	
1-17-78	A-848	L.J.	6-1-170	A-97	L.J.

NO. DATE REVISIONS — DWG. NO. BY

NO. DATE REVISIONS — DWG. NO. BY

APPROVED
CHIEF, PLANNING DIVISION
DATE

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT
EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT
WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS
JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS
JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS
THE PORT OF NEW YORK AUTHORITY — PAVING, UTILITIES, FOUNDATIONS

TITLE: TOWER SECTION SECTION 'B'

DRAWN	E.P.C.	CHECKED	
SCALE	1/16"	DATE	6-1-70
PROJECT		DATE	
SUBMITTED		DATE	
APPROVED		DATE	

DRAWING NO. A-A-176

1/16"=1'-0" 0 1' 2' 3' 4' 8' 12'