NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS FINISH SCHEDULE, DOOR, SCHEDULES AND SCHEDULE OF DRAWINGS SEE DRAWINGS A-0.0.1 TO A-0.0.5.
2. FOR COMPLETE 3rd SMALL FLOOR PLAN SEE DRAWING A-2.0.3.
3. ALL ELEVATIONS GIVEN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUT SEE ELECTRICAL & MECHANICAL DRAWINGS.
5. FOR TYPICAL TOILET DETAILS SEE DWGS. A-2.0.1 AND A-2.0.2.
6. FINISH FLOOR ELEVATION (TOP OF SLAB ELEVATIONS ARE (-0.17") UNLESS OTHERWISE SHOWN OR NOTED.
7. WHERE NO SUSPENDED CEILING IS CALLED FOR, SUCH AS IN CLOSETS, STAIR LANDINGS ETC. BOTTOM ELEVATION OF ALL PIPES AND THEIR COVERING SHALL BE 8'-0" MINIMUM (8'-6" ACTUAL) INCLUDING IN ELEVATOR, SHAFTS AND SHALL BE MEASURED VERTICALLY FROM HORIZONTAL SEE TYPICAL DETAILS.
8. FOR TYPICAL PARTITIONS DETAILS SEE DRAWINGS A-2.0.5 TO A-2.0.10.

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT NO. DRAWING date 6-9-66

NO.	DATE	DWG. NO.	BY
		5-15-67	A-33	L.L.
		5-23-67	A-23	S.L.P.
		5-29-67	A-26	S.L.P.
		5-29-67	A-17	S.L.P.
		6-9-66	A-17	-V.L.
6	6-10-7	A-106	D.S.	6	6-11-67	A-16	V.L.
5	9-12-70	A-72	L.M.	5	8-1-66	A-10	C.G.
4	5-12-70	A-79	L.M.	4	6-23-66	A-5	C.G.
3	1-30-70	A-88	L.L.	3	6-29-66	A-2	C.G.
2	10-30-70	A-97	L.L.	2	8-16-66		V.L.
1				1			

REVISIONS

APPROVED: CHIEF, PLANNING DIVISION — DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 3rd FLOOR CORE PLAN

DESIGN | CHECKED
SCALE: 1/8"=1'-0" | DATE: 7-20-67
PROJECT NUMBER | DRAWN | ck.
DRAWING NUMBER: A-A-24