NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SYMBOLS SEE DRAWINGS A-0.1 TO A-0.4.
2. FOR COMPLETE 1/8" SCALE FLOOR PLAN SEE DRAWING A-4.26
3. ALL ELEVATIONS GIVEN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL TOILET DETAILS SEE DWGS. A-4.0-304 AND A-4.0-306.
6. FINISH FLOOR ELEVATION (TOP OF SLAB ELEVATIONS ARE (F.O.S.+0'-0") UNLESS OTHERWISE SHOWN OR NOTED.
7. WHERE DIMENSIONED COLUMNS ARE CALLED FOR, SAME AS N CLOSETS STORE, PASSAGE ETC., BOTTOM ELEVATION OF ALL PIPES AND DUCTWORK SHALL BE MAINTAINED AT 8'-6" MINIMUM TO PROVIDE FOR EITHER CEILING FIXTURES AND CORNICES OR FULL HEIGHT DOORS.
8. CANTS ALLOWED ON ALL SOLAR PROJECTIONS OVER 24" PROJECTION (4" MAXIMUM) DIMENSIONS IN ELEVATION, PLANTS AND SHALL BE MINIMUM 70° FROM HORIZONTAL. SEE TYPICAL DETAILS.
9. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-4.0-316 TO A-4.0-319

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT	NO	DRAWING	date 2-9-68
		1-20-70	A-17
		5-23-67	A-32
		5-29-69	A-25
		8-29-69	A-26
		6-11-69	A-17
		6-11-69	A-69
6-15-71	A-194	8-1-69	A-10
5-13-70	A-79	6-29-66	A-5
5-13-70	A-79	4-29-66	A-5
1-20-70	A-69	8-18-65	

REVISIONS

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

1/8"-1'-0"

TITLE: 4TH FLOOR CORE PLAN

DRAWING NUMBER: A-A-26