NORTH

NOTES

1. FOR GENERAL NOTES KEY TO NOTE(S) SYMBOLS, ABBREVIATIONS FOR DIV. NUMBERS, AXIS DESIGNATIONS, AND SYMBOLISM SEE DRAWINGS A-0.1 TO A-0.5
2. FOR COMPLETE "E" SCALE PLANS, KEY PLAN SEE DRAWING A-0.01
3. ALL DIMENSIONS GIVEN THUS (10'-0"-) ARE IN RELATION TO FINISH FLOORS.
4. FOR MECHANICAL AND ELECTRICAL LEGENDS SEE DRAWINGS SHEET NOS.
5. FOR TYPICAL STAIR DETAILS SEE DWG^S A-3.5-006 AND A-3.5-006
6. FINISH FLOOR ELEVATION (10'-0") TOP OF SLAB ELEVATION (10'-0") UNLESS OTHERWISE SHOWN OR NOTED.
7. WHERE NO SUSPENDED CEILING IS CALLED FOR, SUCH AS IN TOILETS, STAIRS, MATERIALS ETC., BOTTOM ELEVATION OF ALL FINISHED SOFFITS SHALL BE CONSTRUCTED AT 8'-0" ABOVE FINISHED FLOOR. TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
8. JOINTS ARE REQUIRED IN ALL SLAB FLOOR FINISHES OVER 24' (GENERAL) DIMENSION IN BOTH THE T-JOINTS AND SHALL BE MINIMUM 75° FROM PERPENDICULAR SEE TYPICAL DETAILS.
9. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-A8.1-005 TO A-A8.1-010.
10. ELEVATION TO TOP OF ALL CONCRETE CURBS TO BE (+0'-8") UNLESS OTHERWISE SHOWN OR NOTED.

NOTES

1. SPRINKLER WATERPROOFING AT TOP OF SLAB 1/2" TO 1" CURB AT P.E.
2. TYPE OF MEMBRANE WATERPROOFING TO EXTEND ALL CURBS SEE TYPICAL DETAILS ON DWG^S A-3.5-011, 012 & 013.
3. FOR DEPTH OF SUMP PITS FOR REFRIGERANT, FOUNDATION DWG. A-3.5-006.
4. FOR FINAL SIZE & LOCATION OF CONCRETE PADS SEE M.E.P.C. & PLUMBING CONTRACTORS DRAWINGS.
5. REMOVE FORMS, CHANNEL SUPPORTS, ALL ROD & BOLT PROJECTIONS IN PARTITIONS SEE DETAILS A-A8.1-005.
6. WHERE FINISHED FLOOR IS RAISED ABOVE (10'-0"), FLOOR SHALL BE 3/4" CEMENT FINISH OVER 3" CONCRETE FILLED PANS ON 2" SLAB.
7. PROVIDE 2" RIGID INSULATION AT UNDERSIDE OF MECHANICAL EQUIPMENT ROOM FLOOR.

MECHANICAL EQUIPMENT ROOM

Col. #702 & #707

Col. #705

Col. #802 & #806

Col. #805

COLUMN DETAILS

CONTRACT NO.	DRAWING - date 6-1-68
1. 69-76 A-201	1. A-10-70 A-47
2. 6-1-70 A-167	2. A-20-C1 A-17
3. 1-15-70 A-199	3. A-20-01 A-17
4. 1-20-71 A-222	4. E-15-01 A-23
5. 6-8-71 A-164	5. 1-1-69 A-17
6. 1-5-70 A-108	6. A-1-69 A-93
7. 8-3-70 A-85	7. 11-1-68 A-8
8. 8-6-70 A-79	8. 6-1-68 A-10
9. 8-28-70 A-89	9. A-23-A-5 A-6
10. 8-28-70 A-89	10. E-8-68 E-1

DATE - BUIL. NO. - BY

REVISIONS

DATE - BUIL. NO. - BY

REVISIONS

BULLETINS NOT LISTED ARE IN THE PREVIOUS 24" CONSTRUCTION

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
ARCHIT. UTILITIES/FOUNDATIONS

TITLE: 7TH FLOOR CORE PLAN
LOWER MECH EQUIP ROOM LEVEL

SCALE: 1/16"=1'-0" | DRAWING NO. 7

DATE: 7-29-68 | CONTRACT NO.

A-A-32