NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, PAVING SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAINAGE SEE DRAWINGS A-A-0-1 TO A-A-0-8
2. FOR COMPLETE "B" SCALE PLANS, PLANS "SEE" DRAWING A-A-0-1
3. ALL ELEVATIONS GIVEN THUS (0'-0") ARE IN RELATION TO PAVING PLANS.
4. FOR MECHANICAL AND ELECTRICAL LAYOUT, SEE ADJACENT ENGINEER DRAWINGS
5. FOR TYPICAL STAIR DETAILS SEE DRAWING A-A-0-204 (1-46-204)
6. ALL TRENCHES ASSUMED TO BE BACKFILLED AT UNDERSIDE OF SLAB.
7. FOR A WIDTH OF 6'-0" WITH A SHELF ON TWO SIDES FOR MECHANICAL ENGINEER'S AND CONTRACTOR'S USE. SEE DRAWING A-A-0-201 FOR LOCATION AND EXTENT OF TRENCH HEADERS AND FILLED SLABS.
8. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE EQUAL UNLESS OTHERWISE SHOWN OR NOTED.
9. PAPER TOWEL DISPENSERS IN MEN AND WOMEN TOILET AND DISPENSER AT EACH LAVATORY. EXACT DISPENSER MODELS TO BE LOCATED IN ACCORDANCE WITH THE COVERING. SEE TYPICAL TOILET DETAILS, DRAWING A-A-0-216.
10. WALLS OR ENCLOSED COLUMNS ABUTTING FURRED AREAS SUCH AS IN CLOSETS, STAIR, PASSAGES ETC., BOTTOM ELEVATION OF ALL FURRED AND DUCTWORK SHALL BE MAINTAINED AT 8'-0" ABOVE FINISHED FLOOR, TO ALLOW FOR INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
11. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: _____
12. CANTS ARE REQUIRED ON ALL SLAB PERIPHERIES OVER 25" MINIMUM (OPTIMUM) DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MAXIMUM 75° FROM HORIZONTAL. SEE TYPICAL DETAILS.
13. FOR FIREPROOFING OF FREE STANDING COLUMNS AND TYPICAL PARTITIONS DETAILS SEE DRAWINGS A-A-0-206 THRU A-A-0-211.

NORTH

PART PLAN AT 27TH FLOOR

PART PLAN AT 31ST FLOOR

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT	BID	DRAWING	DATE	BUL. NO.	BY
			11-6-70	A-108	L.L.
			3-8-70	A-78	A.L.
			1-30-70	A-61	L.L.
			1-30-70	A-58	L.L.
			1-30-70	A-47	E.C.
			8-13-69	A-31	R.T.A.
			12-13-68	A-26	L.L.
A	11-15-68	A-345	11-14-68	A-17	L.L.
A	6-18-71	A-170	6-25-68	A-25	L.L.
A	6-8-71	A-166	2-6-68	A-10	D.B.

REVISIONS

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS — EMERY ROTH, RICHARD ROTH, ARCHITECTS

WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — ENGINEERS

THE PORT OF NEW YORK AUTHORITY — PAVING, UTILITIES, FOUNDATIONS

TITLE: 27TH TO 31ST FL. CORE PLAN

1/8" = 1'0"

DRAWN | CHECKED | DATE 4-7-67

SCALE | SHEET

DRAWING NO. A-A-52