NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS AND SCHEDULES, SEE DRAWING A-49.
2. ALL DIMENSIONS ARE TO FACE OF CONCRETE OR MASONRY UNLESS OTHERWISE NOTED.
3. ALL ELEVATIONS GIVEN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LEGENDS, SEE DRAWING A-49 AND ELECTRICAL DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG. NO. A-6.4-5.2 & A-6.4-5.3.
6. ALL TRADES WORKING TO BE PROTECTED AT UNPROTECTED OPENINGS AND AT EDGE OF SLAB ON A NORTH OR SOUTH EXPOSURE AS REQUIRED BY LAW. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND METHOD. ALL PROPERTY LINE FENCING, WHETHER TEMPORARY OR PERMANENT, SHALL BE OF SOLID CONSTRUCTION AND APPROVED BY THE PORT AUTHORITY BEFORE ERECTION. SEE SPECIFICATIONS FOR TYPE, LOCATION AND HEIGHT OF TEMPORARY FENCING AND HOARDINGS.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (U.O.N.) UNLESS OTHERWISE SHOWN ON A-6.1-10.
8. TOILET AND DRESSING ROOMS FOR MEN AND WOMEN TOILET AND DRESSING ROOMS FOR MEN AND WOMEN SHALL BE PROVIDED AT EACH FLOOR WHERE WORK IS BEING PERFORMED. LOCATION OF SUCH TOILETS AND DRESSING ROOMS SHALL BE AS DIRECTED BY THE ENGINEER IN ACCORDANCE WITH THIS CONTRACT.
9. REF. TYPICAL TOILET ROOM DETAILS, SHEET NO. A-6.4-5.1 FOR ACT AS IT COVERS THE FURRED STEEL STUD ELEMENTS OF THE WALLS AND PARTITIONS, WHICH SHALL BE CONSTRUCTED OF 3/4" GYPSUM BOARD, FULL TO STRUCTURE ABOVE. ALL OTHER PARTITIONS SHALL BE FURRED AS NOTED ON DRAWINGS AND INSTALLED AND CEILINGS AS PER THESE DRAWINGS.
10. EXTENT OF PUBLIC CORRIDOR, CEILING IS INDICATED THUS
11. CANTS ARE PROVIDED AT ALL SEMI-PROJECTIONS WITH 45° MITERED (4" MINIMUM) CONCRETE OR MASONRY, SLOPED ALONG THEIR LENGTH. CANTS SHALL BE MINIMUM 12" FROM WALL/SOFFIT. SEE TYPICAL DETAILS.
12. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-6.4-5.1 TO A-6.4-5.3.

TEL CL N.W. (TOP OF SLAB EL. +0'-4")
ELEC CL N. (TOP OF SLAB EL. +0'-4")
TEL CL N.E. (TOP OF SLAB EL. +0'-4")
STEAM SHAFT
S.A. SHAFT
A.C. SHAFT
STAIR 1
STAIR 2
ELEV. LOBBY
ESCALATOR A-2
ESCALATOR A-3
A.C. PIPE SHAFT
10'-7"
MEN
WOMEN
CLOSET
ELEC. CL. C
SERVICE ROOM
CORRIDOR
AIR CONDITIONING ROOM
ELEVATOR
RUNDY
ELEVATOR RUNDY
TEL CL S.W. (TOP OF SLAB EL. +0'-4")
ELEC. CL. S. (TOP OF SLAB EL. +0'-4")
TEL CL S.E. (TOP OF SLAB EL. +0'-4")
COLUMN DETAILS
SCALE: 1/4"=1'-0"
COL. C-201
COL. C-202

BUT LETTING NOT DATED ARE IN AS FAR AS THEY ARE CONSISTENT

CONTRACT NO.		DRAWING	date 2-1-66	
		1-30-70	A-48	LJL
		1-30-70	A-47	EC
		1-30-70	A-46	EC
2-17-68	A-176	5-19-69	A-8	EC
10-27-69	A-100	8-28-69	A-81	ATH
	A-164	3-25-69	A-26	LJL
6-8-70	A-166	3-25-69	A-17	LJL
8-8-71	A-166	3-25-69	A-15	LJL
11-5-70	A-100	8-4-70	A-10	DIG
11-30-70	A-81	11-23-66	A-6	DIG

REVISIONS

REVISIONS

REGISTERED ARCHITECT

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, COORDINATION

1/8"-1'-0"

TITLE: 45TH FLOOR CORE PLAN
UPPER ESCALATOR LEVEL

DRAWN		CHECKED	
SCALE	1/8"=1'-0"	DATE	2-1-66
PROJECT NUMBER		SHEET	76
REVISED NUMBER			A-A-75