NORTH

NOTES:

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND IDENTITIES OF DRAWINGS SEE DRAWINGS A-0.1 TO A-0.4.
2. FOR COMPLETE 1/8" SCALE, FLOOR PLAN SEE DRAWING A-2.1-80
3. ALL ELEVATIONS GIVEN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LEGENDS, SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWGS. A.S.D.-206 AND A.S.D.-205.
6. ALL TRENCH HEADERS TO BE RE-ENFORCED AT UNDERSIDE OF SLAB FOR A WIDTH OF 6'-0" WITH A REINF. MESH TYPE OF REINFORCING SEE ON CONTR. TYPICAL SPECIFICATIONS FOR TYPE. ELECTRICAL ENGINEERS & CONTRACTORS SHALL BE RESPONSIBLE FOR LOCATION & EXTENT OF TRENCH HEADERS & RE-ENFORCING.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (+0'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. SECURITY DESK DIMENSIONS AS SHOWN & TYPICAL DWG DIFFERS AT EACH LOCATION. ACCESS DOORS TO BE PROVIDED WHERE REQUIRED FOR MAINTENANCE OF THE PIPING & DUCTWORK. DETAILS ON DRAWING A-4.05-014.
9. SHAFT OR RECESSED CEILING ARE CALLED FOR, SUCH AS IN CORRIDORS, TOILET ROOMS ETC., SECTION ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR, TO PROVIDE FOR ACTUAL CEILING INSTALLATION AND CLEARANCE FOR SPRINKLER SYSTEMS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: ——————
11. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 24" MINIMUM (2" DETAIL) DIMENSION IN ELEVATION, CANTS ALSO SHALL BE PROVIDED AT ALL PANEL ANGLES OVER 135°. SEE TYPICAL DETAILS.
12. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-A0-206 TO A-A0-212.

COL. 901 — COL. 903

COL. 905 — COL. 902 & 907

COLUMN DETAILS
SCALE 1/2"=1'-0"

NOTE: FOR DETAILS DIMENSIONS FINISHES & SLAB SEE A-2.1 SERIES 200 ELEVATION LOBBY DETAILS DWGS. A-2.1-210

CONTRACT NO. DRAWING date 5-1-68

| | | | | | |
|---|---|---|---|---|---|
| | | | 1-10-70 | A-81 | L.A. |
| | | | 1-30-70 | A-82 | L.A. |
| | | | 1-30-70 | A-83 | L.A. |
| | | | 5-29-69 | A-0 | R.C. |
| | | | 5-29-69 | A-31 | R.C. |
| 5-29-68 | A-376 | L.A. | 5-23-69 | A-16 | R.P. |
| | A-865 | L.A. | 5-23-69 | A-17 | R.P. |
| 6-18-71 | A-864 | R.B.L. | 5-23-69 | A-23 | R.P. |
| 11-6-70 | A-109 | L.A. | 5-4-68 | A-40 | R.C. |
| 5-28-70 | A-78 | L.A. | 5-10-68 | A-6 | R.C. |

NO. DATE DESCRIPTION BY — REVISIONS

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

REGISTERED ARCHITECT — NEW YORK

APPROVED: CHIEF, PLANNING DIVISION — DATE

# THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

| | |
|---|---|
| MINORU YAMASAKI & ASSOCIATES<br>MINORU YAMASAKI, ARCHITECT | EMERY ROTH & SONS<br>RICHARD ROTH, ARCHITECT |
| WORTHINGTON, SKILLING, HELLE & JACKSON<br>STRUCTURAL ENGINEERS | JAROS, BAUM & BOLLES<br>MECHANICAL ENGINEERS |
| JOSEPH R. LORING & ASSOCIATES<br>ELECTRICAL ENGINEERS | THE PORT OF NEW YORK AUTHORITY<br>PAVING, UTILITIES & DRAINAGE |

TITLE: 40TH FLOOR CORE PLAN

| | | | |
|---|---|---|---|
| DRAWN | L.A. | CHECKED | |
| SCALE | 1/8"=1'-0" | DATE | 7-21-67 |
| PROJECT NUMBER | | SHEET | OF |
| DRAWING NUMBER | A-A-81 | | |