NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS #A1 TO A-4-9.
2. FOR COMPLETE 9" SCALE FLOOR PLAN SEE DRAWING A-4-97.
3. ALL ELEVATIONS GIVEN THUS (50'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS' DRAWINGS.
5. FOR TYPICAL DETAILS, DETAILS SEE DWGS #A-4-0-904 AND A-4-8-906.
6. ALL 17-INCH HEADERS TO BE FABRICATED AT UNDERSIDE OF SLAB FOR A WIDTH OF 5'-0" WITH A SPACER ON TOP OF FABRICATING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE & ELECTRICAL ENGINEER'S & CONTRACTOR'S APPLICATION SHOP DRAWINGS FOR LOCATION & EXTENT OF TRENCH HEADERS & FABRICATING.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (NOTED UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS. ONE DISPENSER AT EACH LAVATORY. ACCESS DOORS TO SOAP DISPENSERS WHERE TO BE LOCATED IN BULKHEADS WITH TILE COVERING, SEE TYPICAL DWG #A-4-8-904.
9. WHERE NO HAND GRIPS ARE CALLED FOR, DOOR AS IN CLOSETS, STORE ROOMS ETC., BOTTOM ELEVATION OF ALL PIPES AND DUCTWORK SHALL BE MAINTAINED AT 6'-8" ABOVE FINISHED FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF ALL HEAVY DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS _____
11. UNITS ARE REMOVABLE ON ALL BEAM PROJECTIONS OVER 12" NOMINAL (9" ACTUAL) PROJECTION IN ELEVATION, SHAPED AND SHALL BE MINIMUM 7/8" FURRING HORIZONTAL. SEE TYPICAL DETAILS
12. FOR TREATMENT OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-4-8-904 TO A-4-8-908

SECTION (A/97)

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT BID - DRAWING date 6-1-68

			1	1.30.70	A-89	E.J.
			1	1.30.70	A-97	E.C.
			1	5.25.68	A-91	D.L.
			1	5.31.68	A-86	D.L.
			1	5.23.68	A-17	D.L.
1	6-18-70	A-184	DEL	1	5.23.68	A-83	D.L.
1	6-18-70	A-168	DEL	1	11-1-68	A-91	D.L.
1	9-1-70	A-183		1	8-1-68	A-40	E.C.
1	8-18-70	A-78	E.H.	1	6-18-68	A-2	E.C.
1	1.30.70	A-91	A.S.	1	5-18-68		D.L.

REVISIONS | REVISIONS

REGISTERED ARCHITECT — STATE OF NEW YORK — No. 11,910

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY — PAVING, UTILITIES, FOUNDATIONS

TITLE: 63rd FLOOR CORE PLAN

SCALE: 1/8"-1'-0" | DATE: 8-1-68

PROJECT NUMBER | SHEET NUMBER

A-A-99