NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND TERMINALS OF DRAWINGS SEE DRAWINGS A-1.0-1 TO A-1.0-5
2. FOR CHANGES IN SCALE, FLOOR PLAN SEE DRAWING
3. ALL ELEVATIONS GIVEN THUS (80'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEER'S DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG. #A-10-004 AND A-10-005
6. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 2'-0" WITH A SPRAY-ON TYPE FIREPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEER AND CONTRACTORS APPROVED SHOP DWGS., FOR LOCATION & EXTENT OF TRENCH HEADERS AND FIREPROOFING.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (2'-0"-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE RSM DISPENSERS AT ALL MEN AND WOMEN'S TOILETS. ONE DISPENSER AT EACH LAVATORY. ACCESS DOORS TO SOAP DISPENSER TO BE LOCATED IN ACCORDANCE WITH THE COUNSING. SEE TYPICAL TOILET DETAILS DWG #A-10-014
9. WHERE NO RUNG CLEARANCE ARE CALLED FOR, SUCH AS IN CLOSETS, STAIR PASSAGE ETC. BOTTOM ELEVATION OF ALL RUNS AND BOTTOMS SHALL SHALL BE MAINTAINED AT 11'-8" ABOVE FINISHED FLOOR, TO PROVIDE FOR HEIGHT CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: — — — — —
11. CAUTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 8" NOMINAL (8" ACTUAL) DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 7½" FROM ADJACENT. SEE TYPICAL DETAIL.
12. FOR FIREPROOFING OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DWG. A AB-304 TO A AB-312

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION.

CONTRACT BID DRAWING date 5-1-68

NO.	DATE	BUL. NO.	BY
5	5-29-70	B-48	A.K.
4	9-29-69	B-36	E.C.
3	9-29-69	B-34	E.C.
2	9-29-69	B-31	E.C.
1	9-29-69	B-15	E.C.
	9-29-69	B-25	E.C.
	9-29-69	B-18	E.C.
8-24-72	8-25-72	L.V.	
6-26-71	8-113	D.T.	
1-20-71	B-84	L.V.	

REVISIONS

NO.	DATE	BUL. NO.	BY
9	9-29-69	B-12	E.C.
8	5-1-68	B-6	K.H.
7	5-1-68	B-1	D.G.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 67TH FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	¼"-1'-0"	DATE	7-31-67
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-B-113		

¼"=1'-0" 0 1' 2' 3' 4' 8' 12'