NORTH

NOTES

A. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-A0-1 TO A-A0-04.

B. FOR CONTRACTS & SCALE, FLOOR PLAN SEE DWG. # A-B-146

C. ALL ELEVATIONS GIVEN THUS (10'-0") ARE IN RELATION TO FINISH FLOOR.

D. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS

E. FOR TYPICAL STAIR, OPTIONALS SEE DWGS #A-A0-504 AND A-A0-506.

F. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 2'-0" WITH A SPRAY-ON TYPE FIREPROOFING SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELEC. ENGINEERS & CONTRACTORS SHOP DWGS. FOR LOCATION & EXTENT OF TRENCH HEADER AND FIRE PROOFING

G. FINISH FLOOR, ELEVATION AND TOP OF SLAB ELEVATIONS ARE (100'-0") UNLESS OTHERWISE SHOWN OR NOTED.

H. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS, ONE DISPENSER AT EACH LAVATORY. ACCESS DOORS TO SOAP DISPENSE VALVES TO BE LOCATED IN RECESSES WITH TILE COVERING. SEE TYPICAL TOILET DETAILS DRAWING "A-A8-104.

I. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS, STAIR ENCLOSURES ETC. BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR TO ALLOW FOR PROPER CEILING INSTALLATION AND CLEARANCE OF ALL HEIGHT DOORS.

J. EXTENT OF PUBLIC CORRIDOR, IS INDICATED THUS: .....

1. JOINTS ARE TO BE LOCATED IN ALL BEAM WALLS AT 25'-0" MAXIMUM, IN WALLS AT MAXIMUM DIMENSION IN BETWEEN OPENINGS AND SHALL BE MINIMUM 10'-0" FROM NEAREST OPENING. SEE TYPICAL DETAILS FOR EXPANSION AND CONTROL JOINTS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-B3-306 TO A-B3-312

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT .80 DRAWING Date 3-1-68

NO.	DATE	BUL. NO.	BY
1	1-24-71	B-64	L.J.
2	11-24-70	B-78	L.J.
3	5-22-70	B-65	L.J.
4	7-29-69	B-81	L.J.
5	7-29-69	B-68	L.J.
6	7-29-69	B-72	E.C.
7	7-29-69	B-69	E.C.
8	7-29-69	B-80	E.C.
9	7-29-69	B-78	E.C.
10	8-1-68	B-6	R.T.H.
11	8-26-71	B-116	D.T.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

1/4"=1'-0" 0 1' 2' 3' 4' 8' 12'

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 82ND FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	1/8" = 1'-0"	DATE	7-31-07
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-B-145		