NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-0.01 TO A-0.04.
2. FOR COMPLETE ⅛" SCALE FLOOR PLAN SEE DRAWING A-B-146
3. ALL ELEVATIONS GIVEN THUS (00'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEER'S DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DRAWINGS A-A-704 AND A-A-705
6. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 8'0" WITH A SPRAY-ON 1½" FIREPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELEC ENGINEERS AND CONTRACTORS APPROVED SHOP DRAWINGS FOR LOCATION AND EXTENT OF TRENCH HEADER AND FIREPROOFING.
7. FINISH FLOOR ELEVATION 1 TOP OF SLAB ELEVATIONS ARE (0'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS, ONE DISPENSER AT EACH LAVATORY. ACCESS DOORS TO SOAP DISPENSERS WALKER TO BE LOCATED IN ACCORDANCE WITH TILE LOCATIONS. SEE TYPICAL TOILET DETAILS ON A-A-124.
9. WHERE NO RECESSED OUTLETS ARE CALLED FOR SUCH AS IN CLOSETS, STAIR PASSAGES ETC. BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR, TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: _____
11. CANTS ARE 6"x6"x½" - IN ALL REAL (IN-DIRECTION) OVERALL DIMENSIONS (EXCEPTING ACTUAL) DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 7½" FROM HORIZONTAL. SEE TYPICAL DETAIL.
12. FOR FIREPROOFING OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-A-124 TO A-A-126

COL. "501"

COL. "502" & "507"

COL. "503"

COL. "504"

COL. "505"

COL. "506"

COLUMN DETAILS

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION.

CONTRACT SEQUENCING date 8-1-68

NO.	DATE	ISSUE NO.	BY
A	12-9-70	B-227	L.L.
A	6-28-71	B-318	L.L.

REVISIONS

NO.	DATE	ISSUE NO.	BY
A	1-20-71	B-264	L.L.
A	1-29-71	B-266	L.L.
A	11-24-70	B-172	L.L.
A	9-28-70	B-81	L.L.
A	9-28-70	B-88	L.L.
A	8-26-69	B-19	DG
A	8-26-69	P-16	DG
A	8-26-69	P-108	DG
A	7-24-69	P-15	DG
A	8-1-68	B-0	R.M.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 83rd FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	⅛"=1'-0"	DATE	7-31-67
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-B-147		