NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES, AND SCHEDULES OF DRAWINGS SEE SHEET A-B-1 TO A-B-3.
2. FOR CONCRETE & SCALE FLOOR PLAN SEE DRAWING # A-B-153
3. ALL ELEVATIONS GIVEN THUS (76'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL NOTES SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL FOUR DETAILS SEE SHEET # A-B-204 AND A-B-205
6. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 16'-0" WITH 1" SPRAY-ON TYPE FIREPROOFING. SEE ARCHITECTURAL SPECIFICATION FOR TYPE AND BASIC ENGINEER'S & CONTRACTORS APPROVED SHOP DWGS FOR LOCATION & EXTENT OF TRENCH AND FIREPROOFING.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (76'-0") UNLESS OTHERWISE SHOWN ON PLANS.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS. ONE DISPENSER AT EACH LAVATORY ACCESS DOORS TO SOAP DISPENSER VALVES TO BE LOCATED IN ACCORDANCE WITH TILE ENGRAVING. SEE TYPICAL TOILET DETAILS ON SHEETS A-B-204.
9. NUMBER OF SUSPENDED CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS, TOILET FACILITIES ETC., BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE MAINTAINED AT 8'-0" ABOVE FINISHED FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AN CLEARANCE OF 6'-8" ALL WRIGHT DOORS.
10. EXTENT OF OVERHEAD CEILING IS INDICATED THUS: _____
11. CAUTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 15" NOMINALLY AS DIMENSIONED ON ELEVATOR SHAFTS AND SHALL BE MINIMUM 75" FROM HORIZONTAL. SEE TYPICAL DETAILS.
12. FOR FIREPROOFING OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-AB-306 TO A-AB-312

CORRIDOR

ELEV. LOBBY

SERVICE ROOM

U.D. MAIL RM.

MAIL ROOM

PART PLAN AT 93rd FLOOR

PART PLAN AT 97TH FLOOR

AIR CONDITIONING RM. EXPANSION TANK RM.

PART PLAN AT 93RD FLOOR

COLUMN DETAILS

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT BID DRAWING NO. B-1-GB

NO.	DATE	BUL. NO.	BY
11	11-16-76	B-370	L.R.
10	10-9-72	B-287	L.R.
9	7-7-72	B-186	L.L.
8	8-24-71	B-111	GBL
7	8-24-71	B-116	D.T.
6	1-20-71	B-84	L.L.

REVISIONS

NO.	DATE	BUL. NO.	BY
5	1-27-71	B-85	L.L.
4	11-24-70	B-78	L.L.
3	5-29-70	B-45	A.H.
2	9-29-69	B-21	L.L.
1	9-29-69	B-19	L.L.
	9-29-69	B-12	E.C.
	9-29-69	B-16	E.C.
	9-29-69	B-25	E.C.
	9-29-69	B-13	E.C.
	8-1-68	B-6	A.H.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

1/4"=1'-0" 0 1' 2' 3' 4' 8' 16'

TITLE: 89TH TO 93RD FL CORE PLAN

DRAWN | CHECKED

SCALE: 1/4"=1'-0" | DATE: 7-31-67

PROJECT NUMBERS | SHEET OF

DRAWING NUMBER: A-B-154