AB-156

NORTH

NOTE:
FIREPROOF DUCTS ABOVE WITH 5 LAMINATE LAYERS OF METAL LATH AND 1" GYPSUM CETE PLASTER HARD TO DUCTS. SEE MECH. SPECS. FOR EXTENT OF FIREPROOFING.

CORRIDOR

SECONDARY MOTOR ROOM

ELEV. LOBBY

NOTE:
1. FOR DIMENSIONS AND SLAB DEPRESSIONS SEE ELEVATOR, LOBBY DETAIL AND FLOOR DETAIL DRAWINGS.
2. SEE TENANT ARCH. SPECS FOR DETAILS AND FINISH.

POWDER RM. #1

POWDER RM. #2

WOMEN #1

WOMEN #2

CLOSET

CLOSET (MEN'S ROOM)

SERVICE ROOM

SAIRA SHAFT

A.C. SHAFT

STAIR #1

STAIR #2

ELEV. SHAFT

PIPE SHAFT

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWING # A-A-1 TO A-A-9.
2. FOR COMPLETE 1/8" SCALE FLOOR PLAN SEE DRAWING # A-B-15E
3. ALL ELEVATIONS GIVEN THUS (101'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS
5. FOR TYPICAL STAIR DETAILS SEE DWGS # A-A-20A AND A-A-20C.
6. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 6'-0" WITH A SPRAY-ON TYPE FIREPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELEC. ENGINEER & CONTRACTOR'S APPROVED SHOP DWGS FOR LOCATION & EXTENT OF TRENCH HEADER AND FIREPROOFING.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (101'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS. ONE DISPENSER AT EACH LAVATORY. ACCESS TO SOAP DISPENSER VALVES TO BE LOCATED IN ACCORDANCE WITH TILE DRAWING. SEE TYPICAL TOILET DETAILS DWG. # LAB-2/4.
9. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR SUCH AS IN CLOSETS, STAIR PASSAGES ETC. BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE MAINTAINED AT SAME ABOVE FINISHED FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR, CEILING IS INDICATED THUS: _____
11. CAVITY AREA REQUIRED P.C.F. BELOW PROJECTION O.H. 12 INCHES. CAVITY AREA REQUIRED P.C.F. ABOVE ELEVATOR SHAFT AND WALLS A MINIMUM OF 1 FOOT ON CENTER SEE TYPICAL DETAILS
12. FOR PARTITIONING OF FULL STORY WIDTH COLUMNS AND TYPICAL FURRING DETAILS SEE DRAWINGS A-AP-10.1 A-AP-10.2

BULLETIN 3 ISSUED, DETAILS OF THE PROCESS TO BE DETERMINED

CONTRACT	BID	DRAWING date 3-1-68

NO.	DATE	BUL. NO.	BY
1	1-24-71	B-55	L.J.
2	5-27-70	B-46	A.M.
3	9-29-69	B-37	L.J.
4	9-29-69	B-38	L.K.
5	9-29-69	B-12	D.G.
6	9-29-69	B-18	D.G.
7	9-29-69	B-26	D.G.
8	9-29-69	B-13	D.G.
9	8-1-68	B-6	R.T.H.
10	6-1-68	B-1	D.G.

REVISIONS

NO.	DATE	BUL. NO.	BY
1	8-24-73	B-88E	D.S.
2	10-9-73	B-93	L.B.
3	8-24-71	B-118	D.T.
4	1-24-71	B-24E	L.J.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER
THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 94TH FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	1/16"	DATE	7-31-67
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-B-156		