AB-161

North

NOTE:
FIREWOOD DUCTS ABOVE WITH 5" SEPARATE LAYERS OF METAL LATH AND 1" VERMICULITE PLASTER MADE TO DUCTS. SEE MECH. ENGR. FOR EXTENT OF FURRINGDOWN.

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS # A.B-1 TO A.B-9.
2. FOR COMPLETE "B" SCALE FLOOR PLAN SEE DRAWING # A.B-160
3. ALL ELEVATIONS GIVEN THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWING.
5. FOR TYPICAL JOINT DETAILS SEE DWGS # A.B-204 AND A.B-205.
6. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 6'-0" WITH A SPRAY-ON TYPE FIREPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEER'S AND CONTRACTOR'S APPROVED SHOP DRAWINGS FOR LOCATION AND EXTENT OF TRENCH HEADER AND FIREPROOFING.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (101'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS: ONE DISPENSER AT EACH LAVATORY. ACCESS DOORS TO REAR DISPENSER WALLS TO BE LOCATED IN ACCORDANCE WITH CODE RULING TR-8. SEE TYPICAL TOILET DETAILS DWG. # A.B-214.
9. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR SUCH AS IN CLOSETS, STAIR LANDINGS ETC., BOTTOM ELEVATION OF ALL FURRING AND SOFFITS SHALL BE MAINTAINED AT ELEVATIONS JUST BELOW FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE TO FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: _____
11. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 2" NO. (ACTUAL DIMENSION) IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 75° FROM HORIZ. SEE TYPICAL DETAILS.
12. FOR FIREPROOFING OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS, A.B-206 TO A.B-215.

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT BID DRAWING date 3-1-68

NO.	DATE	BUL. NO.	BY
4	10-9-73	B-287	L.J.
3	9-13-71	B-196	L.J.
2	6-28-71	B-118	D.T.
1	11-29-71	B-54	L.J.

REVISIONS

NO.	DATE	BUL. NO.	BY
10	1-20-72	B-355	L.J.
9	11-24-70	B-72	L.J.
8	9-29-69	B-21	L.J.
7	9-20-69	B-89	L.J.
6	9-19-69	B-13	L.J.
5	9-19-69	B-18	L.J.
4	9-19-69	B-25	L.J.
3	9-20-68	B-13	L.J.
2	5-1-68	B-6	R.T.A.
1	5-1-68	B-1	C.G.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT — NEW YORK STATE — NO. 035 — 26

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 101ST FLOOR CORE PLAN

1/16" = 1'-0"

DRAWN		CHECKED	
SCALE	1/16" = 1'-0"	DATE	7-3-72
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A·B·161		