AB-166

NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS # A-B-1 TO A-B-6.
2. FOR COMPLETE 16" SCALE FLOOR PLAN SEE DRAWING #A-B-105
3. ALL ELEVATIONS GIVEN THUS (100'0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEER'S DRAWING
5. FOR TYPICAL STAIR, DETAILS SEE DWGS# A-B-504 AND A-B-505.
6. ALL TRENCH HEADERS TO BE WATERPROOFED AT UNDERSIDE OF SLAB MIN. 3 MILS OF 4'0" WITH A SPRAYED TYPE WATERPROOFING, SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEER'S AND CONTRACTORS APPROVED SHOP DRAWING FOR LOCATION AND EXTENT OF TRENCH HEADER AND WATERPROOFING.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (100'0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS, ONE DISPENSER AT EACH LAVATORY. ACCESS DOORS TO SOAP DISPENSER VALVES TO BE LOCATED IN ACCORDANCE WITH TILE COUNSIL SEE TYPICAL TOILET DETAILS DRAWING #A-AB-214.
9. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR SUCH AS IN CLOSETS, STAIR PASSAGES ETC, BOTTOM ELEVATION OF ALL BEAMS AND DUCTWORK TO BE MAINTAINED AT 8'-0" ABOVE FINISHED FLOOR TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: _____
11. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 15" NOMINAL (6" ACTUAL) DIMENSION, IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 75° FROM HORIZONTAL SEE TYPICAL DETAIL.
12. FOR PARTITIONING OF FULL HEIGHT COLUMNS AND TYPICAL TOILET DETAILS SEE DRAWING A-AB-211 & A-AB-214.

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT BID DRAWING date 3-1-68

NO.	DATE	BUL. NO.	BY
1	1-28-71	B-94	ALT
10	11-24-70	B-72	L.V.
6	5-27-70	B-48	A.W.
7	9-29-69	B-81	L.V.
4	11-29-68	B-55	L.V.
3	9-29-68	B-12	D.G.
2	9-29-68	B-15	D.G.
1	9-29-68	B-20	D.G.
11	9-29-67	B-13	D.G.
5	8-1-68	B-6	E.H.
1	10-7-73	B-197	M.G.
2	8-26-71	B-116	D.T.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT NEW YORK STATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 104TH FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	1/16"	DATE	7-31-67
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-B-166		