AB-170

NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS FINISH SCHEDULES, DOOR, SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWING # A-A-1 TO A-A-10.
2. FOR COMPLETE 8" SCALE FLOOR PLAN SEE DRAWING # A-B-47
3. ALL ELEVATIONS GIVEN THUS (100'0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS' DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWGS # A-B-904 AND A-B-905
6. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 6'-0" WITH 1 SPRAY-ON TYPE FIREPROOFING. SEE ARCHITECTURAL SPECIFICATIONS FOR TYPE AND ELECTRICAL ENGINEERS AND CONTRACTORS APPROVED SHOP DRAWINGS FOR LENGTHS AND EXTENT OF TRENCH HEADERS AND FIREPROOFING.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATION ARE (66'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE SOAP DISPENSERS AT ALL MEN AND WOMEN'S TOILETS, ONE DISPENSER AT EACH LAVATORY. ACCESS DOORS TO SOAP DISPENSER VALVES TO BE LOCATED IN ACCORDANCE WITH TILE COURSING. SEE TYPICAL TOILET DETAILS DRAWING # A-A-314.
9. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR, SUCH AS IN CLOSETS, STAIR PASSAGES ETC, BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR, TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS: _____
11. CANTS ARE [illegible]
12. FOR [illegible]
DETAILS SEE DRAWING # A-A-314.

BULLETINS NOT DATED ARE IN THE PROCESS OF ISSUANCE

CONTRACT	BID	DRAWING	date 3-1-68

NO.	DATE	BUL. NO.	BY
1	1-8-75	B-281	LJ
2	9-17-75	B-298	DS
3	9-25-76	B-377	RS
4	11-18-76	B-370	JA
5	10-9-78	B-537	LB
6	9-7-79	B-648	LC
7	8-26-81	B-111	DBL
8	8-26-81	B-113	DT
9	6-28-82	B-11	DG
10	1-29-91	B-542	

REVISIONS

NO.	DATE	BUL. NO.	BY
11	11-26-76	B-412	LJ
12	5-23-80	B-483	AM
13	9-29-81	B-581	LJ
14	9-29-82	B-686	LJ
15	9-27-89	B-12	DG
16	9-27-89	B-16	DG
17	9-27-89	B-15	DG
18	9-27-89	B-17	DG
19	8-1-68	B-6	RTM
20	5-1-68	B-1	TDG

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

3/4"=1'-0" 0 1' 2' 3' 4' 8' 12'

TITLE: 106TH FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	1/4"=1'-0"	DATE	7-31-07
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-B-170		