NORTH

NOTES

FOR GENERAL NOTES, KEYS TO MATERIALS SYMBOLS, ABBREVIATIONS, DOOR SCHEDULES AND SCHEDULE OF DRAWINGS SEE DRAWINGS A-0.1 TO A-0.4.

2. FOR COMPLETE ⅛" SCALE FLOOR PLAN SEE DRAWING A-B.171
3. ALL ELEVATIONS GIVEN THUS (10'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DRAWING A-AB.306 & A-AB.206
6. ALL TRENCH HEADERS TO BE FIREPROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 8'-0" WITH A SPRAY ON TYPE FIREPROOFING SEE ARCHITECTURAL SPECIFICATIONS FOR "F.P." AND ELECTRICAL ENGINEERS AND CONTRACTORS APPROVED SHOP DRAWINGS FOR LOCATION & EXTENT OF TRENCH HEADERS & F.P. FIREPROOFING
7. T.F.S.H. FLOOR ELEVATION AND TOP OF SLAB ELEVATION ARE (12'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR SUCH AS IN CLOSETS, STAIR PASSAGES ETC. BOTTOM ELEVATION OF ALL PIPING & DUCTWORK SHALL BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS
9. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 2½" VERTICAL (3" TOTAL DIMENSION) AT ELEVATOR SHAFTS AND SHALL BE MINIMUM 90° FROM HORIZONTAL SEE TYPICAL DETAILS
10. FOR FIREPROOFING OF FREE STANDING COLUMNS AND TYPICAL PARTITION DETAILS SEE DRAWINGS A-AB.206 TO A-AB.211
11. ALL WALLS & PARTITIONS SHOWN IN THIS CONTRACT, ALL WORK NOT MATCHED IS AS A SEPARATE CONTRACT, BY OTHERS. WHERE WORK BY OTHERS INTERSECTS WORK IN THIS CONTRACT CONTRACTORS SHALL COORDINATE ALL WORK SO THAT COMPLETED WORK IS CONTINUOUS AND UNBROKEN. DIMENSIONS SHOWN FOR WORK BY OTHERS IS FOR COORDINATION ONLY.
12. EXTENT OF PUBLIC CORRIDOR CEILING IS INDICATED THUS ———

SECTION (A/172) THRU STAIR #3

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT	BID	DRAWING	date 3-1-68			
			7-7-78	B-143	L.C.
			6-24-71	B-116	D.T.
			4-19-71	B-11	D.G.
9-17-76	B-238	L.J.	1-29-71	B-84	W.H.
1-8-75	B-201	L.J.	6-4-70	B-78	L.J.
9-23-74	B-177	R.E.	9-29-69	B-12	R.T.H.
10-9-73	B-157	L.B.	9-29-69	B-13	R.T.H.
7-24-73	B-135	M.G.	9-29-69	B-13	R.T.H.
3-3-72	B-108	L.C.	8-1-68	B-6	R.T.H.
2-7-72	B-144	L.C.	5-1-68	B-1	D.G.

NO. DATE BUL. NO. BY — REVISIONS

NO. DATE BUL. NO. BY — REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

SKILLING, HELLE, CHRISTIANSEN, ROBERTSON — STRUCTURAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS

EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT

JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY — PAVING UTILITIES, FOUNDATIONS

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT

TITLE: 107TH FLOOR CORE — OBSERVATION LEVEL

DRAWN		CHECKED	
SCALE	1/4" = 1'-0"	DATE	7-31-07
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A·B·172		

1/4"=1'-0" 0 1' 2' 3' 4' 8' 12'