AB-176

NORTH

Notes:

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS ABBREVIATIONS, FINISH SCHEDULE, DOOR SCHEDULE AND SCHEDULE OF DRAWINGS SEE DRAWING "A-A-1 TO A-A-6."
2. FOR COMPLETE "G" SCALE FLOOR PLAN SEE DWG. "A-B-176."
3. ALL ELEVATIONS GIVEN THUS (± 0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FINISH FLOOR ELEVATIONS (± 0'-0") TOP OF SLAB ELEV. (-0'-2") UNLESS OTHERWISE SHOWN ON NOTED.
6. FOR TYPICAL STAIR DETAILS SEE DRAWINGS "A-AB-906 AND A-AB-905."
7. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 3/4" NOMINAL (3/4" ACTUAL) DIMENSION IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 75° FROM HORIZONTAL SEE TYPICAL DETAILS.
8. ELEVATION TO TOP OF ALL CONCRETE CURBS TO BE (+0'-8") UNLESS OTHERWISE SHOWN OR NOTED.

Mechanical Equipment Room

Notes

1. MEMBRANE WATERPROOFING AT TOP OF SLAB WITH 2" CEMENT OVER.
2. TURN UP MEMBRANE WATERPROOFING AT ALL CURBS. SEE TYPICAL DETAILS DRAWINGS "A-AB-906 & A-AB-911."
3. FOR DETAILS OF CONCRETE PADS FOR MECHANICAL EQUIPMENT SEE DRAWING "A-AB-956."
4. FOR PIPE SIZE AND LOCATION OF CONCRETE PADS SEE H.V.A.C. AND PLUMBING CONTRACTORS DRAWINGS.
5. PROVIDE PLANK CHANNEL SUPPORTS OVER ALL MAJOR SHAFT OPENINGS IN PARTITIONS. SEE DETAILS ON DWG. "A-AB-916."
6. WHERE FINISH FLOOR IS RAISED ABOVE (+0'-0") FLOOR SHALL BE 6" CEMENT FINISH OVER HIGH DENSITY 6LB FOAM FILL.
7. PROVIDE 8" RIGID INSULATION AT UNDERSIDE OF MECHANICAL EQUIPMENT ROOM FLOOR.
8. PROVIDE TROLLEY BEAMS, TROLLEYS AND LIFTING RINGS AS REQUIRED. SEE SPECIFICATIONS, STRUCTURAL, MECHANICAL, ELECTRICAL AND ELEVATOR CONTRACTORS APPROVED SHOP DRAWINGS FOR DETAIL OF LIFTING RING SEE DRAWING "A-B-0."

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT BID DRAWING date 3-1-68

NO.	DATE	BUL. NO.	BY
	5-22-70	B-68	A.R.
	5-22-70	B-68	A.R.
	9-29-69	B-81	L.J.
	9-29-69	B-112	E.C.
	9-29-69	B-118	E.C.
	9-29-69	B-119	E.C.
	9-29-69	B-120	E.C.
	9-29-69	B-113	E.C.
	11-1-68	B-7	M.M.
	5-1-68	B-6	R.T.H.

REVISIONS

NO.	DATE	BUL. NO.	BY
1	9-23-76	B-277	W.G.
2	9-14-73	B-195	M.G.
3	5-3-72	B-168	L.C.
4	2-7-72	B-148	L.C.
5	11-23-71	B-136	L.C.
6	8-24-71	B-116	L.J.
7	8-24-71	B-116	L.J.
8	6-29-71	B-11	D.G.
9	1-21-71	B-84	M.M.

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

1/4"=1'-0" 0' 2' 3' 4' 8' 12'

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

SKILLING, HELLE, CHRISTIANSEN, ROBERTSON
STRUCTURAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING UTILITIES, FOUNDATIONS

TITLE: 108TH FLOOR CORE PLAN
LOWER MECH. EQUIP. RM. LEVEL

DRAWN	L.M.M.	CHECKED	
SCALE	1/4"=1'-0"	DATE	7-31-67
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A·B·176		