NORTH

NOTES

1. FOR GENERAL NOTES KEY TO MATERIALS SYMBOLS ABBREVIATIONS FINISH SCHEDULES DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-A-1 TO A-A-5
2. FOR COMPLETE 'G' SCALE FLOOR PLAN SEE DRAWING A-B-32
3. ALL ELEVATIONS GIVEN, THUS (+0'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWGS. A-AB-506 AND A-AB-508
6. SHOW FLOOR ELEVATION (+0'-0"), TOP OF SLAB ELEVATION (-0'-8") UNLESS OTHERWISE SHOWN ON LAYOUT.
7. WHERE NO SUSPENDED CEILING IS CALLED FOR, SUCH AS IN CLOSETS, STAIRS, PASSAGES, ETC., BOTTOM ELEVATION OF ALL BEAMS AND DUCTWORK SHALL BE MAINTAINED AT 8'-4" ABOVE FINISHED FLOOR, TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
8. JOINTS REQUIRED ON ALL BEAM PROJECTIONS OVER 12" NOMINAL (12" ACTUAL) DIMENSION, IN ELEVATOR SHAFTS SHALL BE MINIMUM 2" MASAN VIBRA-CONTROL, SEE TYPICAL DETAILS
9. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-AB-506 TO A-AB-516
10. ELEVATION TO TOP OF ALL CONCRETE CURBS TO BE (+0'-8") UNLESS OTHERWISE SHOWN OR NOTED

NOTES

1. NONLEAKAGE WATERPROOFING AT TOP OF SLAB WITH 2" CEMENT FINISH OVER.
2. TOPS OF NONLEAKAGE WATERPROOFING TO (+0'-8") AT ALL CURBS SEE TYPICAL DETAIL ON DWG A-AB-504 & A-AB-511
3. FOR OPENINGS OR CONC. PADS FOR MECHANICAL EQUIPMENT SEE DWG # A-AB-506
4. FOR FINAL SIZE & LOCATION OF CONCRETE PADS SEE H.V.A.C. & PLUMBING CONTRACTORS DRAWINGS.
5. TRACTION PLANKS, CHANNEL SUPPORTS OVER ALL PIT & SHAFT OPENINGS IN PARTITIONS SEE DETAILS A-AB-514
6. WHERE FINISHED FLOOR IS RAISED ABOVE (+0'-0") FLOOR, SHALL BE 2" CEMENT FINISH OVER, HIGH DENSITY RIGID FOAM FILL.
7. PROVIDE 2" RIGID INSULATION AT UNDERSIDE OF MECHANICAL EQUIPMENT ROOM FLOOR.

COLUMN DETAILS
SCALE 3/4"=1'-0"

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

NO.	DATE	BUL. NO.	BY
1	5-8-68	B-167	L.J.
2	5-8-68	B-168	L.C.
3	9-7-70	B-180	L.J.
4	11-23-71	B-...	L.J.
5	11-22-70	B-78	D.G.

REVISIONS

NO.	DATE	BUL. NO.	BY
1	5-22-68	B-80	L.J.
2	5-22-70	B-86	J.W.
3	9-27-68	B-12	D.L.
4	9-27-68	B-9	D.L.
5	9-27-68	B-19	D.L.
6	9-27-68	B-16	D.L.
7	9-27-68	B-13	D.L.
8	11-1-68	B-7	D.G.
9	5-1-69	B-6	D.G.
10	5-1-69	B-1	D.G.

REVISIONS

CONTRACT BID DRAWING date 8-1-68

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT — KINORU YAMASAKI — STATE OF NEW YORK

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

1/8"=1'-0" 0 1' 2' 3' 4' 8' 12'

TITLE: 7TH FLOOR CORE PLAN
LOWER MECH. EQUIP. RM. LEVEL

DRAWN		CHECKED	
SCALE	1/8"=1'-0"	DATE	7-31-69
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-B-33		