NORTH

NOTES:

1. FOR GENERAL NOTES, KEY TO MATERIALS, ABBREVIATIONS, FINISH SCHEDULE, DOOR SCHEDULE & SCHEDULE OF DRAWINGS SEE DRAWING # A-B-1 TO A-B-6
2. FOR COMPLETE 5TH VILLE FLOOR PLAN SEE DWG# A-B-69
3. ALL ELEVATIONS GIVEN THUS (36'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL & ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG.# A-B-206 & A-B-208
6. FINISH FLOOR ELEVATION (101'-0") AND TOP OF SLAB ELEVATION (-6'-8") UNLESS OTHERWISE SHOWN OR NOTED.
7. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR, SUCH AS IN GLOSETS, STONE WASHROOMS ETC., BOTTOM ELEVATION OF ALL FURRING AND PARTITIONS TO BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR, TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
8. CANTS ARE REQUIRED ON BEAM PROJECTIONS OVER 4" IN MINIMUM (8" ACTUAL) DIMENSION, IN DIRECTION OF RUN, AND SHALL BE MINIMUM 10" FROM HORIZONTAL. SEE TYPICAL DETAILS.
9. FOR TYPICAL PARTITION DETAILS SEE DRAWINGS A-B-206 TO A-B-213.
10. ELEVATIONS TO TOP OF ALL CONCRETE SLABS TO BE (-6'-8") UNLESS OTHERWISE SHOWN OR NOTED.

SECTION (4/70) BANK "D"

MECHANICAL EQUIPMENT ROOM

NOTES

1. MEMBRANE WATERPROOFING AT TOP OF SLAB WITH 2" CEM. FIN. TO.
2. TURN UP MEMBRANE WATERPROOFING TO (-6'-8") AT ALL CURB. SEE TYPICAL DETAILS ON DWG. # A-B-B-209 & A-B-B-211
3. FOR DETAILS OF CONC. PAD FOR MECH. EQUIP. SEE DWG # A-AB-602
4. FOR FINAL SIZE & LOCATION OF CONC. PADS SEE M.V.A.C. & PLUMBING CONTRACTORS DRAWINGS.
5. PROVIDE PLANE CHANNEL SUPPORTS OVER ALL FAN & DUCT OPENINGS IN PARTITIONS. SEE DETAILS DWG # A-AB-512
6. WHERE FINISHED FLOOR IS RAISED ABOVE (-6'-0"). FLOOR SHALL BE 2½" CEMENT FINISH OVER HIGH DENSITY RIGID FOAM FILL.
7. PROVIDE 2" RIGID INSULATION AT UNDERSIDE OF MECHANICAL EQUIPMENT ROOM FLOOR.

BULLETINS NOT DATED ARE IN THE PROPOSAL AT COMPLETION
CONTRACT BID - [illegible] Date 5-1-68

NO.	DATE	BUL. NO.	BY
1	1-29-71	B-35	L.L.
2	5-27-70	B-38	A.M.
3	5-27-70	B-48	A.M.
4	9-29-69	B-34	E.C.
5	9-29-69	B-31	E.C.
6	9-29-69	B-18	L.L.
7	9-29-69	B-12	L.L.
8	7-29-69	B-19	L.L.
9	7-29-69	B-24	L.L.
10	7-29-69	B-13	L.L.
11	11-1-68	B-7	K.R.
12	8-1-68	B-6	K.R.
13	5-1-68	B-1	P.G.

REVISIONS

REGISTERED ARCHITECT — MICHAEL J. MESKAN — NO. 31178 — STATE OF NEW YORK

APPROVED

CHIEF, PLANNING DIVISION

DATE

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES — MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS — RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON — STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES — MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES — ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY — PAVING, UTILITIES, FOUNDATIONS

3/16"=1'-0" 0 1/4" 1' 3" 4' 8" 12'

TITLE: 41ST FLOOR CORE PLAN — LOWER MECH. EQUIP. RM. LEVEL

DRAWN		CHECKED	
SCALE	1/16"=1'-0"	DATE	7-31-67
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A·B·70		