NORTH

NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, SYMBOLS, ABBREVIATIONS, FINISH SCHEDULES, DOOR SCHEDULES AND SCHEDULES OF DRAWINGS SEE DRAWINGS A-A-1 TO A-A-6.
2. FOR COMPLETE 1/8" SCALE FLOOR PLAN SEE DRAWING A-B-92.
3. ALL ELEVATIONS GIVEN THUS ('10'-0") ARE IN RELATION TO FINISH FLOOR.
4. FOR MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DWG. # A-A-204 & A-A-205
6. ALL TRENCH HEADERS TO BE FIRE-PROOFED AT UNDERSIDE OF SLAB FOR A WIDTH OF 4'-0" WITH A SPRAY-ON TYPE OF FIRE-PROOFING SEE ARCHITECTURAL SPECIFICATION FOR TYPE & ELECTRICAL ENGINEERS & CONTRACTOR'S APPROVED SHOP DWGS. FOR LOCATION & EXTENT OF TRENCH HEADERS & FIRE-PROOFING.
7. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (10'-0") UNLESS OTHERWISE SHOWN OR NOTED.
8. PROVIDE TOILET DISPENSERS AT MEN AND WOMENS TOILETS. ONE DISPENSER AT EACH LAVATORY ACCESS DOOR TO SOAP DISPENSER VALVES TO BE LOCATED IN ACCORDANCE WITH TILE COURSING. SEE TYPICAL TOILET DETAILS DWG. #A-A-A-214
9. WHERE NO SUSPENDED CEILINGS ARE CALLED FOR, SOFFITS AT IN CLOSETS, STAIR, REFRIGER ETC., BOTTOM ELEVATION OF ALL PIPING AND DUCTWORK SHALL BE MAINTAINED AT 8'-6" ABOVE FINISHED FLOOR. TO PROVIDE FOR FUTURE CEILING INSTALLATION AND CLEARANCE OF FULL HEIGHT DOORS.
10. EXTENT OF PUBLIC CORRIDOR, CEILING IS INDICATED THUS: - - - - - -
11. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 24" NOMINAL (8" ACTUAL) DIMENSION, IN ELEVATOR SHAFTS AND SHALL BE MINIMUM 15° FROM HORIZONTAL.

SEE TYPICAL DETAILS
SEE DWGS. A-A-201 TO A-A-203

SEE TYPICAL DETAILS
SEE DWGS. A-A-206 TO A-A-212

CORRIDOR
SUSP. CEIL. (+8'-6")

ELEV. LOBBY
SUSP. CEIL. (+8'-6")

TENANT SPACE

TENANT SPACE

SECTION A/B-94

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT BID DRAWING date 8-1-68

NO.	DATE	BUL. NO.	BY
8	8-24-70	B-136	LW
7	11-24-70	B-72	LJ
6	6-22-70	B-48	AM

REVISIONS

NO.	DATE	BUL. NO.	BY
5	9-29-69	B-95	EC
4	9-29-69	B-94	EC
3	9-29-69	B-81	EC
2	9-29-69	B-18	EC
1	9-29-69	B-12	EC
	9-29-69	B-25	EC
	9-29-69	B-13	EC
7	11-1-68	B-7	EC
6	8-1-68	B-6	ATA
5	6-1-68	B-1	DG

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION

DATE

REGISTERED ARCHITECT

1/4"=1'-0" 0 1' 2' 3' 4' 8' 12'

THE WORLD TRADE CENTER

THE PORT OF NEW YORK AUTHORITY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

WORTHINGTON, SKILLING, HELLE & JACKSON
STRUCTURAL ENGINEERS

JAROS, BAUM & BOLLES
MECHANICAL ENGINEERS

JOSEPH R. LORING & ASSOCIATES
ELECTRICAL ENGINEERS

THE PORT OF NEW YORK AUTHORITY
PAVING, UTILITIES, FOUNDATIONS

TITLE: 56TH FLOOR CORE PLAN

DRAWN		CHECKED	
SCALE	1/4"=1'-0"	DATE	7-31-69
PROJECT NUMBER		SHEET	OF
DRAWING NUMBER	A-B-94		