SYMBOL KEY FOR INTERNATIONAL PLAZA AREA

- METAL LIGHT TRACK
- FLOURESCENT STRIP LIGHT
- SLIDING METAL GRILLES
- 16" OPEN WEB JOISTS, TOP EL. [+]19'-0"
- AIR DIFFUSER
- DOWN LIGHT
- SPRINKLER HEAD
- LOUDSPEAKER
- DOME LIGHT FIXTURE

NORTH

NOTES:

1. FOR GENERAL NOTES, KEY TO MATERIALS & ABBREVIATIONS, SEE SHEET A-F-1101 E.
2. FOR SCANTLING & MECHANICAL DIMENSIONS SHOWN ON THIS DRAWING, SEE SEPARATE DRAWINGS.
3. FOR PLAN, NOTES & DIMENSIONS ON SCHED. CONTRACT LIGHT LINES FOR FLUORESCENT, SEE DWG. A-F-125.

PASSAGE J

PASSAGE E

MEZZANINE

SLIDING METAL GRILLE

DROPPED PLASTER SOFFIT EL. 320'-5½"

BARE LIGHT BULBS IN PLAS. TROUGHS SEE DWG. A-F-152

PLAS. CEILING EL. 313'-11½"

DROPPED PLASTER SOFFIT EL. 320'-5½"

BOTTOM OF LIGHT IN PLASTER SOFFIT

EXPOSED STRUCTURE

RETURN PLASTER UP TO SLAB ABOVE

9 SLOT CONT. ALUM. AIR DIFFUSER

VISION PANEL WELL

GYP BOARD SOFFIT ON METAL FURRING AT EL. 317'-0" TO CONTINUE FINISH OF INTERIOR, OF VISION PANEL WELL. RETURN GYP. BOARD TO SLAB ABOVE OUTSIDE I'-5" SOFFIT

ROLL-UP DOOR, SEE DETAILS ON DWG #A-F-184

N 4529.50
N 4495.50
N 4465.50
N 4435.50
N 4405.50
N 4376.50
N 4345.50

W 9730.00
W 9700.00
W 9670.00
W 9640.00
W 9610.00
W 9580.00
W 9550.00
W 9520.00

MEZZANINE FLOOR

RECEIVED
OCT 23 1975
SKILLING - HELLE CHRISTIANSEN - ROBERTSON
230 PARK AVE. N.Y.C.

KEY PLAN

BULLETINS NOT DATED ARE IN THE PROCESS OF COMPLETION

CONTRACT BID DRAWING date 11-21-75

NO.	DATE	SUB. NO.	BY
4	9-12-75	F-22	JVL
3		F-16	JK
2	4-1-75	F-2	LJ
1	10-17-75	E-13	LJ
0	11-18-74	ADD'L	LJ
Δ	7-19-74	ADD'L	LJ

REVISIONS

APPROVED

CHIEF, PLANNING DIVISION
DATE

THE WORLD TRADE CENTER

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

SKILLING, HELLE, CHRISTIANSEN, ROBERTSON
STRUCTURAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY
MECHANICAL, ELECTRICAL, PAVING, UTILITIES, FOUNDATIONS

TITLE: SOUTHEAST PLAZA BUILDING #5 & MEZZANINE REFL. CEILING PLAN, SOUTH-WEST.

DRAWN	CHECKED
SCALE 1/8"=1'-0"	DATE 11-15-75
PROJECT NUMBER	SHEET OF
DRAWING NUMBER A-F-147	