NOTES

1. FOR GENERAL NOTES, KEY TO MATERIALS, ABBREVIATIONS, FINISH SCHEDULE, DOOR SCHEDULE & SCHEDULE OF DRAWINGS, SEE DRAWINGS A.P.-1 TO A.P.-5
2. FOR COMPLETE 2 SCALE CORE PLAN SEE DRAWING A.P.-2F
3. ALL ELEVATIONS GIVEN THUS (+21.0') ARE TAKEN IN RELATION TO FINISH FLOOR, WHICH IS ELEVATION 310'-0"
4. FOR ALL MECHANICAL AND ELECTRICAL LAYOUTS SEE RESPECTIVE ENGINEERS' DRAWINGS.
5. FOR TYPICAL STAIR DETAILS SEE DRAWING A.P.-10D
6. FINISH FLOOR ELEVATION AND TOP OF SLAB ELEVATIONS ARE (0'-0") UNLESS OTHERWISE SHOWN OR NOTED.
7. CANTS ARE REQUIRED ON ALL BEAM PROJECTIONS OVER 2" ACTUAL DIMENSION IN ELEVATOR SHAFTS AND WALLS, BE MINIMUM "S" FROM HORIZONTAL SEE TYPICAL DETAILS ON DWG A.P.-12A
8. EXITS AND SUBDIVISION OF TENANT SPACE, TO BE DETERMINED FROM TENANT ARCHITECTS DWGS.
9. PROVIDE IRON LADDERS TO SPRINKLER CONTROL VALVES SEE SPRINKLER DRAWINGS FOR VALVES LOCATIONS.
10. PROVIDE LOOSE LINTELS OVER ALL OPENINGS IN MASONRY WALLS EXCEPT AS OTHERWISE SHOWN OR NOTED SEE MECHANICAL DRAWINGS.
11. FIREPROOF DUCTS BETWEEN TENANCIES WITH 2 SEPARATE LAYERS OF METAL LATH & 1" VERMICULITE PLASTER, HARD TO DUCTS, FOR EXTENT OF FIREPROOFING, SEE MECHANICAL DRAWINGS.

RECEIVED
OCT 23 1975
SKILLING-HELLE CHRISTIANSEN-ROBERTSON
230 PARK AVE. N.Y.C.

CONTRACT BID DRAWING date 11-21-75

NO.	DAT	REVISIONS	BUL. NO.	BY
3	9-15-75	F-22		LK
4	10-17-75	F-13		LK
5	11-15-75	REV #2		C.G.
6	7-17-74	REV #1		L.H.
7	11-19-73	ADD #1		GD.

APPROVED
CHIEF, PLANNING DIVISION
DATE

THE WORLD TRADE CENTER

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY

MINORU YAMASAKI & ASSOCIATES
MINORU YAMASAKI, ARCHITECT

SKILLING, HELLE, CHRISTIANSEN, ROBERTSON
STRUCTURAL ENGINEERS

EMERY ROTH & SONS
RICHARD ROTH, ARCHITECT

THE PORT AUTHORITY OF NEW YORK AND NEW JERSEY
MECHANICAL, ELECTRICAL, PIPING, UTILITIES, FOUNDATIONS

TITLE: SOUTHEAST PLAZA BUILDING 1ST FLOOR - 30'-0" LEVEL SOUTHWEST

DRAWN	CHECKED
SCALE 1/8" = 1'-0"	DATE 11-15-75
PROJECT NUMBER	SHEET - OF
DRAWING NUMBER	A.P.-9S